## Z1000 Family of Drives



# **YASKAWA**

**HVAC Building Automation Catalog** 

## A Single Drive for all Your Building Automation Needs

The Z1000 variable-speed drive is designed for building automation applications such as fans, pumps, and cooling towers through 500 HP. The Z1000 features HVAC-specific application macros, an easy-to-read LCD keypad that provides Hand-Off-Auto interface, and a real time clock. These features make the Z1000 perfect for most building automation applications that require reliable motor control.

#### **Pushing Expectations**

Yaskawa America, Inc. has been building packages for the HVAC industry since 1988. Over that time, we have worked rigorously to evolve our products and exceed industry standards, while ensuring an exceptional customer experience.

Our latest offering for the HVAC industry, the Z1000 family of drives, pushes past the standard requirements to establish a new benchmark for expectations within the industry.

Yaskawa embraces the challenge of supplying an essential product into a growing and changing market. Customers of all types are demanding more flexibility, more control, more power, less downtime, and more packaging options. The Z1000 family of drives is able to address and exceed all of these expectations.



Z1000 Drive	es estate de la constant de la const		8
	Z1000 Drive		8
		Z1000 Specifications: 200 to 240 and 380 to 480 V	8
		Z1000 Specifications: 500 to 600 V	9
		Z1000 Model Selection 200 to 240 V	10
		Z1000 Model Selection 380 to 480 V	10
		Z1000 Model Selection 500 to 600 V	11
		Z1000 Options	12
		Z1000 Dimensions and Data	<i>17</i>
	Bypass Drive NEMA Type 1 (Z1B1)		19
		Specifications: 208 and 480 V NEMA Type 1	19
		Model Number Configuration	20
		Options	<i>20</i>
		Model and Power Option Selection	22
		Dimensions and Data	24
	Z1000 Bypass Drive NEMA Type 12 (Z1BB)		26
		Specifications: 208 and 480 V NEMA Type 12	26
		Model Number Configuration	27
		Options	27
		Model and Power Option Selection	29
		Dimensions and Data	31
	Bypass Drive NEMA Type 3R (Z1B3)		33
		Specifications: 208 and 480 V NEMA Type 3R	<i>3</i> 3
		Model Number Configuration	<i>34</i>
		Options	<i>34</i>
		Model and Power Option Selection	<i>3</i> 6
		Dimensions and Data	<i>3</i> 8
	Z1000 Configured Drive NEMA Type 1 (Z1C1)		40
		Specifications: 208 and 480 V NEMA Type 1	40
		Model Number Configuration	41
		Options	41
		Model and Power Option Selection	43
		Dimensions and Data	45
	Configured Drive NEMA Type 12 (Z1CB)		47
		Specifications: 208 and 480 V NEMA Type 12	47
		Model Number Configuration	48
		Options	48
		Model and Power Option Selection	50
		Dimensions and Data	52

Configured Drive NEMA Type 3R (Z1C3)		<i>54</i>
	Specifications: 208 and 480 V NEMA Type 3R	54
	Model Number Configuration	<i>55</i>
	Options	56
	Model and Power Option Selection	58
	Dimensions and Data	60
Redundant Drive Package NEMA Type 1 (Z1R1)		62
	Specifications: 480 V NEMA Type 1	62
	Model Number Configuration	63
	Options	<i>63</i>
	Model Selection	64
(Z1000) Drives		65
12-Pulse Bypass Drive NEMA Type 1 (Z1B1J)		<i>65</i>
	Specifications: 480 V NEMA Type 1	65
	Model Number Configuration	66
	Options	66
	Model and Power Option Selection	67
12-Pulse Bypass Drive NEMA Type 3R (Z1B3J)		68
	Specifications: 7.5 to 250 HP, 480 V NEMA Type 3R	68
	Model Number Configuration	69
	Options	69
	Model and Power Option Selection	<i>71</i>
12-Pulse Configured Drive NEMA Type 1 (Z1C1J)		<i>7</i> 2
	Specifications: 7.5 to 250 HP, 480 V NEMA Type 1	72
	Model Number Configuration	73
	Options	<i>73</i>
	Model Selection	74
12-Pulse Configured Drive NEMA Type 3R		<i>7</i> 5
(Z1C3J)	Charifications, 400 V/NEMA Torre 7D	
	Specifications: 480 V NEMA Type 3R	75 76
	Model Number Configuration	<i>7</i> 6
	Options  Madel and Bower Option Selection	<i>7</i> 6
	Model and Power Option Selection	<i>77</i>
18-Pulse Bypass Drive NEMA Type 1 (Z1B1K)		<i>7</i> 8
	Specifications: 480 V NEMA Type 1	<i>7</i> 8
	Model Number Configuration	<i>7</i> 9
	Options	<i>7</i> 9
	Model and Power Option Selection	80

	18-Pulse Bypass Drive NEMA Type 3R (Z1B3K)		81
		Specifications: 480 V NEMA Type 3R	<i>81</i>
		Model Number Configuration	82
		Options	<i>82</i>
		Model and Power Option Selection	84
	18-Pulse Configured Drive NEMA Type 1 (Z1C1K)		85
		Specifications: 480 V NEMA Type 1	<i>85</i>
		Model Number Configuration	86
		Options	86
		Model and Power Option Selection	<i>87</i>
	18-Pulse Configured Drive NEMA Type 3R (Z1C3K)		88
		Specifications: 480 V NEMA Type 3R	88
		Model Number Configuration	89
		Options	89
		Model and Power Option Selection	90
Z1000U H	IVAC MATRIX Drives		91
	Z1000U HVAC MATRIX Drive		91
		Z1000U Specifications: 200 to 240 V and 380 to 480 V	91
		Z1000U Model Selection 200 to 240 V	92
		Z1000U Model Selection 380 to 480 V	92
		Z1000U Options	93
		Z1000U Dimensions and Data	97
	Z1000U Bypass Drive NEMA Type 1 (Z1D1)		98
		Specifications: 208 and 480 V NEMA Type 1	98
		Model Number Configuration	99
		Options	99
	Z1000U Bypass Drive Type 12 (Z1D2)		103
		Specifications: 480 V Type 12	103
		Model Number Configuration	104
		Options	104
	Z1000U Bypass Drive NEMA Type 3R (Z1D3)		107
		Specifications: 208 and 480 V NEMA Type 3R	<i>107</i>
		Model Number Configuration	108
		Options	108
	Z1000U Configured Drive NEMA Type 1 (Z1E1)		113
		Specifications: 208 and 480 V NEMA Type 1	113
		Model Number Configuration	114
		Options	114
	Z1000U Configured Drive Type 12 (Z1E2)		118
		Specifications: 480 V Type 12	118

	Model Number Configuration	119
	Options	<i>11</i> 9
Z1000U Configured Drive NEMA Type 3R (Z1E3)		123
	Specifications: 208 and 480 V NEMA Type 3R	and 480 V NEMA Type 3R 123
	Model Number Configuration	124
	Options	124
Technical Training		128

## Preface

This catalog may describe trademarked equipment, which is the property of other companies. These trademarks are the property of the registered owner companies and may include the following:

APOGEE®, FLN is a registered trademark of Siemens Building Technologies, Inc.

APOGEE®, Anywhere™ is a trademark of Siemens Building Technologies, Inc.

BACnet is a trademark of the American Society of Heating, Refrigerating, and Air-Conditioning Engineers (ASHRAE).

Metasys®, N2 is a trademark of Johnson Controls, Inc.

Modbus®, trademark of Schneider Automation, Inc.

Other Documents and Manuals are available to support special use or installation of this product.

These documents may be provided with the product or upon request. Contact Yaskawa America, Inc. or visit www.yaskawa.com, as required.

### Z1000 Specifications: 200 to 240 V and 380 to 480 V



The Z1000 variable-speed drive is engineered for use in HVAC building automation applications requiring reliable motor control.

The Z1000 features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy. Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 3 to 150 HP, 200 to 240 Vac 3 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Motor preheat function
- · Adjustable accel/decel: 0.1 to 6000 seconds
- · Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 30 to 180%
- Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection
- Up/down floating point control capability
- · Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage: 200 to 240 Vac, 380 to 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating
- Service factor: 1.0
- Vibration: 9.81 m/s² (1 G) maximum at 10 to 20 Hz, 2.0 m/s² (0.2 G) at 20 Hz to 55 Hz
- Plenum mounting capable (IP20)
- RoHS Compliant

#### **Design Features**

- Built in 5% line impedance (3 to 100 HP @ 208V, 3 to 250 HP @ 480V)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (3 to 100 HP @ 208V, 3 to 250 HP @ 480V)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PI) Controls
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- Feedback signal low pass filter
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication
- · Diagnostic fault indication

- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 2 amps @ 250 Vac & 30 Vdc)
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions with a built-in copy feature
- · Motor preheat function
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508C (Power Conversion)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- UL 1995 (Plenum)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed; CE marked
- IBC 2012

#### Options

- · LonWorks Interface
- EtherNet/IP
- Modbus TCP/IP

### Z1000 Specifications: 500 to 600 V



The Z1000 variable-speed drive is engineered for use in HVAC building automation applications requiring reliable motor control.

The Z1000 features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: 2 to 250 HP
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Motor preheat function
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 30 180%
- · Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- · Serial communications loss detection
- · Up/down floating point control capability
- Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5 kHz
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage:
   575 600 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating
- · Service factor: 1.0
- Vibration: 9.81 m/s<sup>2</sup> (1 G) maximum at 10 to 20 Hz, 2.0 m/s<sup>2</sup> (0.2 G) at 20 Hz to 55 Hz
- Plenum mounting capable (IP20)
- · RoHS Compliant

#### **Design Features**

- Displacement power factor of 0.98 throughout the motor speed range
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PI) Controls
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication
- · Diagnostic fault indication

- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 2 amps @ 250 Vac & 30 Vdc)
- 7 preset speeds
- · Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions
- Motor preheat function
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508C (Power Conversion)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- UL, cUL listed; CE marked
- IBC 2012

#### **Options**

- LonWorks Interface
- EtherNet/IP
- Modbus TCP/IP

## Z1000 Drive

#### Z1000 Model Selection 200 to 240 V

**Z1000 Drives** 3 to 150 HP, 200 to 240 V, 3-phase input, NEMA-1/IP20 enclosed or Protected Chassis/IP00.

Rated Input Voltage	Drive Model Number CIMR-ZU	Rated Output Current (Amps)	Nominal HP *1	Standard Enclosure
	2A0011FAA	10.6	3	
	2A0017FAA	16.7	5	
	2A0024FAA	24.2	7.5	
	2A0031FAA	30.8	10	
	2A0046FAA	46.2	15	
	2A0059FAA	59.4	20	NEMA-1 / IP20
	2A0075FAA	74.8	25	
200 to 240 V 3-Phase	2A0088FAA	88	30	
o i nacc	2A0114FAA	114	40	
	2A0143FAA	143	50	
	2A0169FAA	169	60	
	2A0211FAA	211	75	
	2A0273FAA	273	100	
	2A0343AAA	343	125	Onen Tyne / ID00
	2A0396AAA	396	150	Open-Type / IP00

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

### Z1000 Model Selection 380 to 480 V

**Z1000 Drives** 3 to 500 HP, 480 V, 3-phase input, NEMA-1/IP20 enclosed or Protected Chassis/IP00.

Rated Input Voltage	Drive Model Number CIMR-ZU	Rated Output Current (Amps)	Nominal HP *1	Standard Enclosure
	4A0005FAA	4.8	3	
	4A0008FAA	7.6	5	
	4A0011FAA	11	7.5	
	4A0014FAA	14	10	
	4A0021FAA	21	15	
	4A0027FAA	27	20	
	4A0034FAA	34	25	
	4A0040FAA	40	30	
	4A0052FAB	52	40	NEMA-1 / IP20
	4A0052FAA	52	40	NEMA-1/1P20
380-480 V	4A0065FAA	65	50	
3-Phase	4A0077FAA	77	60	
	4A0096FAA	96	75	
	4A0124FAA	124	100	
	4A0156FAA	156	125	
	4A0180FAA	180	150	
	4A0240FAA	240	200	
	4A0302FAA	302	250	
	4A0361AAA	361	300	
	4A0414AAA	414	350	Onen Type / IDCC
	4A0480AAA	480	400	Open-Type / IP00
	4A0590AAA	590	500	

<sup>1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

### **Z1000 Model Selection 500 to 600 V**

Z1000 Drives 1 to 250 HP, 600 V, 3-phase input, NEMA-1/IP20 enclosed or Protected Chassis/IP00.

Detect locate	Boto d Outroot	d Outrat	Standard Enclosure *1 *2
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *3	Drive Model Number CIMR-ZU
	2.7	1 & 2	5A0003FAA
	3.9	3	5A0004FAA
	6.1	5	5A0006FAA
	9	7.5	5A0009FAA
	11	10	5A0011FAA
	17.5	15	5A0017FAA
	22	20	5A0022FAA
	27	25	5A0027FAA
500 to 600 V	32	30	5A0032FAA
3-Phase	41	40	5A0041FAA
	52	50	5A0052FAA
	62	60	5A0062FAA
	77	75	5A0077FAA
	99	100	5A0099FAA
	125	125	5A0125AAA
	145	150	5A0145AAA
	192	200	5A0192AAA
	242	250	5A0242AAA

<sup>\*1.</sup> Standard Enclosure can be conventionally mounted or heat sink external (kit required for models CIMR-ZU5A0032FAA and smaller).

<sup>\*2.</sup> Only models ending in FAA (CIMR-ZU5A0099FAA and smaller) come standard with NEMA 1 End Cap Kits. Separately sold kits are available for larger models.

<sup>\*3.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors. Also, listed power ratings assume three-phase input.

## Z1000 Drive

### **Z1000 Options**

### **End Cap Kits NEMA 1**

This option consists of a top and bottom cover to convert a protected IPOO/Open Type drive to a IP2O/NEMA 1, UL Type 1 enclosed unit. This option DOES NOT provide additional space for mounting auxiliary components (i.e., circuit breaker, input fuses, reactor, etc.).

Rated Input Voltage	Drive Model Number CIMR-ZU2A□□□□	Part Number
200 to 240 V	0343	EZZ021136E
3-Phase	0396	LZZ021130L
Rated Input Voltage	Drive Model Number CIMR-ZU4A□□□□	Part Number
	0361	EZZ021136E
380 to 480 V	0414	UUX000662
3-Phase	0480	UUX000663
	0590	00000063
Rated Input Voltage	Drive Model Number CIMR-ZU5A□□□□	Part Number
	0041 *1	EZZ021136G
	0052 *1	E22021130G
	0062 *1	
	0165 *1	EZZ021136C
500 to 600 V 3-Phase	0099 *1	
5 · //do5	0125	EZZ021136D
	0145	EZZUZTIOOD
	0192	EZZ021136E
	0242	EZZUZTIJUE

<sup>\*1.</sup> These ratings are already available as NEMA 1 (FAA) drives; the End Cap Kits for these ratings are shown here only for replacement purposes.

#### 24 Vdc Control Power Unit

This option provides board-level component voltages for the Z1000 drive when provided with 24 Vdc from an external, customer-supplied source. It is used to maintain both drive control power and network communications (when utilized). Option kits for customer mounting:

Rated Input Nominal HP Drive Model Number CIMR-ZU		Drive Model Number CIMP 711	Control Power Unit
Voltage	Nominal HP	Drive Model Number Clinik-20	Part Number
200 to 240 V 3-Phase	3 through 150	2A0011 through 2A0396	PS-A10LB
380 to 480 V 3-Phase	3 through 500	4A0005 through 4A0590	PS-A10HB
500 to 600 V 3-Phase	2 through 250	5A0003 through 5A0242	PS-A10HB

#### **External Heatsink Kits**

**External Heatsink Kit**: Allow drives to be mounted with the drive's heat sink external to the enclosure. Option kit for customer mounting. Available in either NEMA 1 or NEMA 12.

#### External Heatsink Kits NEMA 1 for 200 to 240 V Models

Rated Input Voltage	Drive Model Number CIMR-ZU2A□□□□	Part Number
	0011	EZZ021811A
	0017	E22021811A
	0024	EZZ021811B
	0031	EZZUZ1811B
	0046	F77004044C
	0059	EZZ021811C
200 to 240 V 3-Phase	0075	
o i naco	0088	EZZ021811D
	0114	
	0143	
	0169	NIA
	0211	N/A
	0273	

#### External Heatsink Kits NEMA 1 for 380 to 480 V Models

Rated Input Voltage	Drive Model Number CIMR-ZU4A□□□□	Part Number
	0005	
	8000	EZZ021811A
	0011	
	0014	
	0021	EZZ021811B
	0027	
	0034	F77004044C
	0040	EZZ021811C
380 to 480 V 3-Phase	0052 *1	
o i nasc	0065	F77004044D
	0077	EZZ021811D
	0096	
	0124	
	0156	
	0180	N/A
	0240	
	0302	

<sup>1.</sup> Use EZZ021811C when using model CIMR-ZU4A0052FAB.

## Z1000 Drive

#### **External Heatsink Kits NEMA 12**

Rated Input Voltage	Drive Model Number CIMR-ZU2A□□□□	Part Number
	0011	EZZ021642A
	0017	L22021042A
	0024	EZZ021642B
	0031	L22021042B
	0046	EZZ021642C
000 to 040 V	0059	220210420
200 to 240 V 3-Phase	0075	
	0088	EZZ021642D
	0114	
	0143	
	0169	EZZ021642F
	0211	L220210421
	0273	
Rated Input Voltage	Drive Model Number CIMR-ZU4A□□□□	Part Number
	0005	
	0008	EZZ021642A
	0011	
	0014	
	0021	EZZ021642B
	0027	
	0034	EZZ021642C
	0040	LZZ021042C
380 to 480 V 3-Phase	0052 <sup>*1</sup>	
0 i ii.do0	0065	EZZ021642D
	0077	LZZ0Z104ZD
	0096	
	0124	EZZ021642E
	0156	
	0180	EZZ021642F
	0240	
	0302	EZZ021642G

<sup>\*1.</sup> Use EZZ021642C when using model CIMR-ZU4A0052FAB.

#### External Heatsink Kits for 500 to 600 V

Rated Input Voltage	Drive Model Number CIMR-ZU5A□□□□	Part Number
	0003	EZZ020800A
	0004	EZZUZU800A
	0006	
	0009	EZZ020800B
500 to 600 V 3-Phase	0011	
o i naco	0017	EZZ020800C
	0022	EZZUZU800C
	0027	F77020900D
	0032	EZZ020800D

## **Control and Communication Options**

These cards, cables, and devices add control functionality to the standard drive. Items are shipped loose, unmounted.

### **Digital Operator and Software**

Model No.	Option Name	Description
UOP000016	Digital Operator (LCD)	This option is the standard digital operator found on the drive. This option is only required if the original digital operator is lost or damaged. If used as a remote operator, the standard digital operator may be used, but then requires Installation Set A (EZZ020642A) for panel or door mounting and Remote Operator Cable (UWR0051 or UWR0052), each sold separately. Features include:
(JVOP-183)	Digital Operator (LCD)	LCD keypad display, 5 lines x 16 characters, backlit
		7 languages
		Copy function
		Mounts to RJ-45 keypad port
EZZ020642A	LCD/LED Keypad Installation Set A (Remote Operator Mounting Bracket Kit)	This is a bracket to which the LCD Digital Remote Operator (JVOP-183) attaches, and has (4) threaded holes and screws to attach to the cover of an enclosure. The kit contains (2) screws to mount the Operator to the bracket and (4) screws to attach the bracket to the enclosure.
EZZ020642B	LCD/LED Keypad Installation Set B (Remote Operator Mounting Bracket Kit)	Contains a similar bracket that the keypad attaches to and has non-threaded holes for mounting to an enclosure that has the screws attached to the enclosure already. The kit contains (2) screws to mount the keypad to the bracket and (4) nuts to attach the bracket to the customer supplied screws attached to the enclosure.
UUX000922	Keypad Adapter Kit	This kit can be used when a "new" Z1000 keypad is replacing an "old style" key pad used with E7-based Z1000 drives. This kit will allow enclosure door mounted key pad to be upgraded from E7 style to the Z1000 style digital key pad.
UWR0051	Operator Cable, Remote (1 meter)	These cables are used to connect the Remote Digital Operator (JVOP-18□). They are available in
UWR0052	Operator Cable, Remote (3 meter)	one (1) or three (3) meter lengths.
UUX000526 (Blank Membrane)		This option is used to extend an LCD or LED Digital Remote Operator to the wall of a separately specified, oversized UL Type 3R, 4, 4X, or 12 enclosure (IPX6 environment). Item includes a
UUX000527 (Yaskawa Logo Membrane)	Operator Kits, NEMA Type 3R/4X	faceplate bezel with digital operator brackets and membrane to cover the operator cutout in the enclosure door, a 3-foot cable, a 10-foot cable, and a 1:1 template for cutting the necessary cutouts in the enclosure. Keypad can be removed after kit installation. Designed for use with <b>1000 series Digital Remote Operators (sold separately)</b> . Connects to RJ-45 port and mounts to enclosure wall.
UNP00233-3 (Yaskawa Logo)	Overlay, Keypad, Self-adhesive	This membrane is used to cover the operator cutout in the enclosure door to which the keypad has been remotely mounted.
UNP00233-5 (Blank)	Overlay, Noypau, oell autiesive	
UOP000017 (Yaskawa Logo Faceplate Membrane)	UL Rated Remote Outdoor Operator/	UL Rated Remote Outdoor Operator / Mounting Kit. This option provides all you will need to remotely mount the drive's Digital Operator to the door/wall of a separately specified, oversized UL Type 1, 3R, 4, 4X, or 12 enclosure (IPX6 environment). This kit includes: One JVOP-183R Digital Operator providing RTC, HOA, and outdoor rated LCD display, a faceplate bezel with digital operator brackets
UOP000019 (Blank Faceplate Membrane)	Mounting Kit	and membrane to cover the operator cutout in the enclosure door, a 3-foot cable, a 10-foot cable, and a 1:1 template for cutting the necessary cutouts in the enclosure. Mounting hardware is included. Keypad can be removed after kit installation. Connects to RJ-45 port and mounts to enclosure wall.
SW.DW.40	DriveWizard® HVAC Software	This optional software package allows upload and download of parameters via PC for data storage and for programming multiple drives. The software also includes graphing and monitoring tools. It is a Windows-based program designed to make startup, commissioning, and troubleshooting the drive as simple as possible. Refer to our website at <b>www.yaskawa.com</b> to download the software, and for more information, including minimum system requirements and cable information to interface a PC to the drive.
UWR-0638	USB Interface Cable	This 10-foot male USB-A to male USB-B cable provides a USB-to-USB connection from PC to the drive.
UWR-01076-1	Flash Write Cable	This 6-foot cable connects a PC's 9-pin serial port to the drive's keypad port for updating the drive's firmware, flashing with custom firmware, or updating a network communication option board. It is used with the Flash Tool feature of the DriveWizard® HVAC software.
UWR00468-2	PC Interface Cable	This 6-foot cable interconnects the drive keypad port to the 9-pin communication port on a PC. This cable is used in conjunction with DriveWizard® HVAC software.

## Z1000 Drive

#### **Support Tools**

Model No.	Option Name	Description
JVOP-181	USB Copy Unit (Y-Stick)	This option allows the drive to connect to the USB port on a PC. It can read, copy and verify drive parameter settings from one drive to another like drive. The unit plugs into the RJ-45 port on the front of the digital operator. Refer to our website at www.yaskawa.com to download the software.
No Model Number	CopyUnitManager Software for USB Copy Unit (Y-Stick)	This option allows the user to transfer and save parameter files from the Copy Unit (JVOP-181), sold separately, to a PC and vice versa. Refer to our website at www.yaskawa.com to download the software.

#### **Network Communications**

Model No.	Option Name	Description				
SI-W3	This option is compatible with the LonMark Interoperability Association and compatible for a Variable Frequency Motor Drive. Network connectivity is a Phoenix-style screw termination or RJ-45 connector.  Mounts at option connector CN5-A.					
SI-EN3	EtherNet/IP	This option complies with the EtherNet/IP protocol specification, and allows for communication over 10/100 Mbps Ethernet networks. This option has the ability to configure the IP Address from a user specified IP address, from a DHCP host, or from a BootP host. The IP address can be set from the drive keypad or from the network. All parameters, diagnostics, and operational commands are accessible via EtherNet/IP. The web interface allows management of diagnostic information through a standard web browser. The embedded web pages include the main page, drive status page, network monitor page, and documentation page. Mounts at option connector CN5-A.				
SI-EM3	Modbus TCP/IP	This option complies with the Modbus TCP/IP protocol specification. This allows for Modbus communication over 10/100 Mbps Ethernet networks. This option has the ability to configure the IP Address from a user-specified IP address, from a DHCP host, or from a BootP host. All parameters, diagnostics, and operational commands are accessible via Modbus TCP/IP. This option supports up to 10 simultaneous PLC/PC connections.  Mounts at option connector CN5-A.				
SI-EN3D	EtherNet/IP with device level ring (DLR)	This option complies with the EtherNet/IP protocol specification. This allows for communication over 10/100 Mbps Ethernet networks. The dual port hardware provides the user the choice of wiring in a star, line or ring configuration. For a ring configuration, device level ring (DLR) is available on this option card. This option has the ability to configure the IP Address from a user specified IP address, from a DHCP host, or from a BootP host. All parameters, diagnostics and operational commands are accessible via EtherNet/IP. Auto-tuning the motor is also possible through this option using the DriveWizard PC program.  Mounts at option connector CN5-A.				
SI-EM3D	Modbus TCP/IP – Dual Port	This option complies with the Modbus TCP/IP protocol specification. This allows for Modbus communication over 10/100 Mbps Ethernet networks. The dual port hardware provides the user the choice of wiring in a star, line or ring configuration. For a ring configuration, rapid spanning tree protocol (RSTP) is available on this option card. This option has the ability to configure the IP Address from a user specified IP address, from a DHCP host, or from a BootP host. All parameters, diagnostics and operational commands are accessible via Modbus TCP/IP. Auto-tuning the motor is also possible through this option using the DriveWizard PC program. This option supports up to 10 simultaneous PLC/PC connections.  Mounts at option connector CN5-A.				

## **Z1000 Dimensions and Data**

### 200 to 240 V

Rated Input Voltage	Drive Model Number	Nominal HP	Physic	cal Dimer (in)	nsions	Weight	Drawing Number	Heat Loss (Watts)		
voitage	CIMR-ZU		Н	W	D	(lb)		Heatsink	Internal	Total
	2A0011FAA	3	14.06		8.58	12.3	DD.Z1K.FR1.N1	121	28	148
	2A0017FAA	5	14.00	4.88		13.0	DD.ZIK.FKI.NI	176	37	214
	2A0024FAA	7.5	17.60	4.00	9.17	16.3	3 DD.Z1K.FR2.N1	280	55	335
	2A0031FAA	10	17.00		9.17 DD.21K.FR2.N1	DD.Z IK.FRZ.N I	378	73	451	
	2A0046FAA	15	20.08	7.87	9.35	26.5	DD.Z1K.FR3.N1	396	86	482
	2A0059FAA	20	20.06	7.07		28.7	DD.ZTK.FR3.NT	542	116	658
	2A0075FAA	25		10.04	10.37	59.5	DD.Z1K.FR4.N1	557	132	688
200 to 240 V 3-Phase	2A0088FAA	30	21.33			61.7		670	157	827
0 1 1.000	2A0114FAA	40				63.9		864	200	1064
	2A0143FAA	50				143.3		1191	307	1499
	2A0169FAA	60	30.47	13.39	15.75	149.9	DD.Z1K.FR6.N1	1447	365	1811
	2A0211FAA	75	30.47	13.39	15.75	154.3	DD.Z IN.FRO.N I	1753	471	2224
-	2A0273FAA	100				160.9		2378	625	3003
	2A0343AAA	125	31.5	19.69	13.78	216.0	DD.Z1K.FR8.IP00	1964	655	2620
	2A0396AAA	150	31.5	19.09	13.76	218.0	DD.Z IN.FRO.IPUU	2435	829	3264

### 380 to 480 V

Rated Input	Drive Model	Nominal	Physica	l Dimens	ions (in)	Weight		Hea	at Loss (Watts	s)
Voltage	Number CIMR-ZU	HP	Н	w	D	(lb)	Drawing Number	Heatsink	Internal	Total
	4A0005FAA	3				11.9		93	24	117
	4A0008FAA	5	14.06		8.58	12.6	DD.Z1K.FR1.N1	143	33	178
	4A0011FAA	7.5	]	4.00		13.4		184	38	222
	4A0014FAA	10		4.88		16.1		231	52	283
	4A0021FAA	15	17.60		9.17	16.8	DD.Z1K.FR2.N1	306	69	375
	4A0027FAA	20	]			18.5		390	85	475
	4A0034FAA	25			9.35			457	105	562
	4A0040FAA	30	20.08	7.87		28.7	DD.Z1K.FR3.N1	558	118	677
	4A0052FAB	40						584	151	734
	4A0052FAA	40		10.04	10.37	59.5		463	130	594
380 to 480 V	4A0065FAA	50	21.33			63.9	DD.Z1K.FR4.N1	576	161	737
3-Phase	4A0077FAA	60				68.3	DD.Z1K.1 K4.W1	891	225	1116
	4A0096FAA	75				70.5		1131	288	1419
	4A0124FAA	100	27.56	10.87	11.38	101.4	DD.Z1K.FR5.N1	1581	398	1979
	4A0156FAA	125				160.9		1929	535	2464
	4A0180FAA	150	30.47	13.39	15.75	167.6	DD.Z1K.FR6.N1	2342	621	2963
	4A0240FAA	200				174.2		2863	790	3653
	4A0302FAA	250	41.14	17.91	18.90	286.6	DD.Z1K.FR7.N1	3278	929	4207
	4A0361AAA	300	31.50	19.70	13.78	236.0	DD.Z1K.FR8.IP00	3009	1157	4166
	4A0414AAA	350	37.40	19.70	14.57	275.0	DD.Z1K.FR9.IP00	3206	1633	4840
	4A0480AAA	400	44.88	26.38	14.57	476.0	DD.Z1K.FR10.IP00	3881	2011	5893
	4A0590AAA	500	44.00	26.38	14.37	487.0	DD.Z1K.I'K10.IP00	4130	1964	6094

## Z1000 Drive

#### 500 to 600 V

Rated Input	Drive Model		Physica	I Dimens	ions (in)	Weight		Hea	at Loss (Watts	s)
Voltage	Number CIMR-ZU	Nominal HP	Н	W	D	(lb)*1	Drawing Number*2	Heatsink	Internal	Total
	5A0003FAA	2	11.81	5.51	5.79	7.5	DD.Z1K6.FR1.N1	23.3	21.5	44.8
	5A0004FAA	3	11.01	5.51	5.79	7.5	DD.ZTKO.FKT.INT	33.6	27.5	61.1
	5A0006FAA	5	44.04	F F4	0.40	0.0	DD 741/0 FD0 N4	43.7	28.1	71.8
	5A0009FAA	7.5	11.81	11.81 5.51 6.46		8.2	DD.Z1K6.FR2.N1	68.9	43.4	112.3
	5A0011FAA	10	11.81	5.51	6.57	9.0	DD.Z1K6.FR3.N1	88	56.1	144.0
	5A0017FAA	15	40.00	7.00	7.00	40.0	DD 741/C EDE NA	146.7	96.6	243.2
	5A0022FAA	20	13.39	7.09	7.36	13.2	DD.Z1K6.FR5.N1	178.3	99.4	277.7
	5A0027FAA	25	45.75	0.00	7.76	40.0	DD 74KC EDC NA	227.2	132.1	359.3
	5A0032FAA	30	15.75	8.66	7.70	19.2	DD.Z1K6.FR6.N1	279.9	141.6	421.5
	5A0041FAA	40	20.20	10.98	10.16	59.5	DD.Z1K6.FR8B.N1	330.8	136.2	467.0
500 to 600 V	5A0052FAA	50	20.28	10.98	10.16	59.5	DD.ZTKO.FR8B.NT	427.8	166.2	594.0
3-Phase	5A0062FAA	60						791.2	279.0	1070.2
	5A0077FAA	75	28.74	12.95	11.14	99.2	DD.Z1K6.FR10.N1	959.1	329.4	1288.5
	5A0099FAA	100						1253.2	411.7	1664.9
	5A0125AAA *3	125	27.76	17.72	12.99	174.2	DD.Z1K6.FR11.IP00	1641	537	2178
	DAU125AAA	125	37.80	17.95	12.99	191.8	DD.Z1K6.FR11.N1	1041	557	2170
	5A0145AAA *3	150	27.76	17.72	12.99	174.2	DD.Z1K6.FR11.IP00	1860	603	2463
	5A0145AAA °	150	37.80	17.95	12.99	191.8	DD.Z1K6.FR11.N1 *3	1000	603	2403
	EA0102AAA *3	200	31.50	19.69	13.78	235.9	DD.Z1K6.FR12.IP00	2420	769	3180
	5A0192AAA *3	200	45.98	19.84	13.78	257.9	DD.Z1K6.FR12A.N1 *3	2420	709	3180
	EA0242AAA *3	250	31.50	19.69	13.78	235.9	DD.Z1K6.FR12.IP00	2100	1121	1004
	5A0242AAA *3	250	45.98	19.84	13.78	257.9	DD.Z1K6.FR12A.N1 *3	3100	1131	4231

<sup>\*1.</sup> This data represents the average drive weight only, not shipping weight.

<sup>\*2.</sup> The drawings are available in .pdf and .dwg formats. For additional formats, click on the Mechanical Drawings link available on the Z1000 Product Details page at www.yaskawa.com.

<sup>\*3.</sup> Protected chassis models can be converted to NEMA Type 1 by adding top and bottom covers. Add-on kit is required. Consult factory for add-on kit.

## Bypass Drive NEMA Type 1 (Z1B1)

### Specifications: 208 and 480 V NEMA Type 1 (Z1B1)



The Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control. The package provides a Z1000 drive in a NEMA 1 (UL Type 1) enclosure with a 2-contactor style bypass to allow motor operation from the drive or across the line.

The bypass features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy. Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: 1 to150 HP, 208 Vac 1 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque

#### **Bypass Features**

- Bypass and Drive output contactors
- · Lockable Main Input disconnect switch
- Thermal motor overload relay, class 20
- · 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable energy savings and harmonic reduction mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Built in 5% line impedance (1 100 HP @ 208 V, 1 - 250 HP @ 480 V)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (1 - 100 HP @ 208 V, 1 - 250 HP @ 480 V)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication
- · Diagnostic fault indication
- Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status

- · 7 preset speeds
- · Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed
- BTL certified

#### Options


- Circuit Breaker (100 kAIC, additional fuses not required)
- 3-Contactor Bypass
- Drive Service Switch
- Input Reactor
- Noise Filter
- Custom Nameplate
- EtherNet/IP
- LonWorks
- Modbus TCP/IP

## Bypass Drive NEMA Type 1 (Z1B1)

### **Model Number Configuration (Z1B1)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1B1)

### **Enclosure Options**

NEMA 1

(1) The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

## **Power Options**

Circuit Breaker	(M)	The standard configuration provides an input disconnect switch with a padlockable operator mechanism. This disconnect switch DOES NOT provide motor short circuit protection. If motor short circuit protection is desired in the bypass enclosure, select option (M), which provides a circuit breaker (100 kAIC) with a padlockable operator mechanism.
Drive Input Circuit	(B, G)	The standard configuration does not include any protection or disconnecting means specifically for the drive. For a 3-contactor bypass that removes power from the drive, select option (B). For an input disconnect switch that removes power from the drive, select option (G).
Input Reactor	(R)	The standard configuration does not provide any additional AC line impedance. Option (R) can be selected to add a 3% AC line input reactor, (For 300 to 500 HP @ 480 volts and 125 to 150 HP @ 208 volts only.)
Input Filter	(N)	The standard configuration for 125 to 150 HP @ 208V and for 300 to 500 HP @ 480V does not include a RFI filter. The cap filter, option (N), is a passive deltawye capacitive network.
Control Options	5	
Ethernet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## Bypass Drive NEMA Type 1 (Z1B1)

## **Model and Power Option Selection (Z1B1)**

### **208 V Models and Power Options**

					Legend:	A = Available	N/A = Not ava	ailable or not ap	plicable
Rated Input Voltage	Rated Output Current	Nominal HP *1	NEMA 1 Bypass	Typical Lead Time	Circuit Breaker (100 kAIC)	Contactor Bypass	Drive Input Service Switch	Input Reactor	Cap Filter
	(Amps)		<b>Z1B1</b> □□□□		M	В	G	R	N
	2.4	0.5	D002						
	3.5	0.75	D003						
	4.6	1	D004	<u> </u>					
	7.5	2	D007						
	10.6	3	D010						
	16.7	5	D016				Α		
	24.2	7.5	D024						
	30.8 10	10	D030	10 Working Days					
	46.2	15	D046					N/A	N/A
208 V	59.4	20	D059		Α	A			
3-Phase	74.8	25	D074		, ,	, ,			
	88	30	D088						
	114	40	D114						
	143	50	D143						
	169	60	D169						
	211	75	D211				N/A		
	273	100	D273						
	343	125	D343	] -					
	396	150	D396					А	Α

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

## **480 V Models and Power Options**

					Legend: A	= Available	N/A = Not ava	ailable or not	applicable
Rated Input Voltage	Rated Output Current	Nominal HP *1	NEMA 1 Bypass	Typical Lead Time	Circuit Breaker (100 kAIC)	Contactor Bypass	Drive Input Service Switch	Input Reactor	Cap Filter
	(Amps)		<b>Z1B1</b> □□□□		М	В	G	R	N
	1.6	0.5 & 0.75	B001						
	2.1	1	B002						
	3.2	2	B003						
	4.8	3	B004						
	7.6	5	B007						
	11	7.5	B011						
	14	10	B014						
	21	15	B021				Α		N/A
	27	20	B027						
	34	25	B034	10 Working Days					
	40	30	B040	Days				N/A	
	52	40	B52L						
480 V 3-Phase	52	40	B052		Α	Α			
o i nasc	65	50	B065						
	77	60	B077						
	96	75	B096						
	124	100	B124						
	156	125	B156						
	180	150	B180						
	240	200	B240				NI/A		
	302	250	B302				N/A	IN/A	
	361	300	B361						
	414	350	B414	-				Δ.	
	477	400	B477					А	A
	590	500	B590	1					

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

## Bypass Drive NEMA Type 1 (Z1B1)

## **Dimensions and Data (Z1B1)**

## 208 V NEMA Type 1

Rated	Z1B Bypass	Rated			Submittal Documents	Drive			ed, NEM ass Data			
Input Voltage	Base No. Z1B1	Output Current (Amps)	Nominal HP	Bypass Box No.	(Outline Drawing) (Schematic)	Part No CIMR-ZU	Overall Dimensions (in)			Weight (lb)		
	0000	` ' '			(Submittal Guide)		Н	W	D	(ID)		
	D002	2.4	0.5			2A0011FAA						
	D003	3.5	0.75			2A0011FAA						
	D004	4.6	1	W1	DD.Z1B1.W1.01 DS.Z1B1.01	2A0011FAA	41.60			70		
	D007	7.5	2		SG.Z1B1.10	2A0011FAA	41.00	0.77	12.92	70		
	D010	10.6	3			2A0011FAA		6.77	12.92			
	D016	16.7	5			2A0017FAA						
	D024	24.2	7.5	W2	14/2	14/2	DD.Z1B1.W2.01 DS.Z1B1.01	2A0024FAA	45.10			80
	D030	30.8	10		SG.Z1B1.10	2A0031FAA	45.10			00		
	D046	46.2	15	14/0	DD.Z1B1.W3.01 DS.Z1B1.01 SG.Z1B1.10	2A0046FAA	40.00	10.10	13.19	90		
	D059	59.4	20	W3		2A0059FAA	48.20	10.18				
208 V 3-Phase	D074	74.8	25	W4	DD.Z1B1.W4.01 DS.Z1B1.01 SG.Z1B1.10	2A0075FAA	52.80	12.68	14.20	160		
	D088	88	30		DD.Z1B1.W5.01	2A0088FAA			40.00			
	D114	114	40	W5	DS.Z1B1.01 SG.Z1B1.10	2A0114FAA	42.79	25.80	16.06	280		
	D143	143	50	11/0	DD.Z1B1.W6.01	2A0143FAA						
	D169	169	60	W6	DS.Z1B1.01 SG.Z1B1.10	2A0169FAA	49.09	28.41	20.87	380		
	D211	211	75	F1	DD.Z1.1.F1.02	2A0211FAA				950		
	D273	273	100		DS.Z1B1.01 SG.Z1B1.10	2A0273FAA	04.40	44.00	22.04	1250		
	D343	343	125		DD.Z1.1.F1.01	2A0343AAA	84.16	41.26	33.94	1650		
	D396	396	150	F1	DS.Z1B1.02 SG.Z1B1.10	2A0396AAA				1700		

## 480 V NEMA Type 1

Rated	Z1B Bypass	Rated			Submittal Documents	Drive			ed, NEM. ass Data	
Input Voltage	Base No. Z1B1	Output Current (Amps)	Nominal HP	Bypass Box No.	(Outline Drawing) (Schematic)	Part No CIMR-ZU	Dim	Overall ensions		Weight (lb)
		` ' '			(Submittal Guide)		Н	W	D	(ID)
	B001	1.6	0.75			4A0005FAA				
	B002	2.1	1			4A0005FAA				
	B003	3.4	2	W1	DD.Z1B1.W1.01 DS.Z1B1.01	4A0005FAA	41.60			70
	B004	4.8	3	V V I	SG.Z1B1.10	4A0005FAA	_ 41.00			70
	B007	7.6	5			4A0008FAA		6.77	12.92	
	B011	11	7.5			4A0011FAA				
	B014	14	10		DD.Z1B1.W2.01	4A0014FAA				80
	B021	21	15	W2	DS.Z1B1.01	4A0021FAA	45.10			
	B027	27	20		SG.Z1B1.10	4A0027FAA				
	B034	34	25	14/0	DD.Z1B1.W3.01	4A0034FAA				
	B040	40	30	W3	DS.Z1B1.01 SG.Z1B1.10	4A0040FAA	40.00	10.10	12.10	90
	B52L	52	40	W3	DD.Z1B1.W3.01 DS.Z1B1.01 SG.Z1B1.10	4A0052FAB	48.20	10.18	13.19	90
480 V	B052	52	40		DD.Z1B1.W4.01	4A0052FAA		12.68	14.20	
3-Phase	B065	65	50	W4	W4 DS.Z1B1.01	4A0065FAA	52.80			160
	B077	77	60		SG.Z1B1.10	4A0077FAA				
	B096	96	75		DD.Z1B1.W5.01	4A0096FAA			40.00	
	B124	124	100	W5	DS.Z1B1.01 SG.Z1B1.10	4A0124FAA	42.79	25.80	16.06	280
	B156	156	125		DD.Z1B1.W6.01	4A0156FAA				
	B180	180	150	W6	DS.Z1B1.01 SG.Z1B1.10	4A0180FAA	49.09	28.41	20.87	380
	B240	240	200	F1	DD.Z1.1.F1.02 DS.Z1B1.01 SG.Z1B1.10	4A0240FAA				1,250
	B302	302	250		DD 71 1 E1 01	4A0302FAA	1	41.26	33.94	1,600
	B361	361	300	F1	DD.Z1.1.F1.01 DS.Z1B1.01	4A0361AAA	84.16			1,700
	B414	414	350		SG.Z1B1.10	4A0414AAA	1			1,800
	B477	477	400		DD.Z1.1.F2.01	4A0477AAA	1			2,100
	B590	590	500	F2	DS.Z1B1.02 SG.Z1B1.10	4A0590AAA	1	69.76	30.50	2,200

## Z1000 Bypass Drive NEMA Type 12 (Z1BB)

### Specifications: 208 and 480 V NEMA Type 12 (Z1BB)



The Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control. The package provides a Z1000 drive in a NEMA 12 (UL Type 12) enclosure with a 2-contactor style bypass to allow motor operation from the drive or across the line.

The bypass features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 1 to150 HP, 208 Vac 1 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
   0 to 10 VDC (20 K Ohm)
  - 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque

#### Bypass Features

- Bypass and Drive output contactors
- Lockable Main Input disconnect switch
- Thermal motor overload relay, class 20
- 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable energy savings and harmonic reduction mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Built in 5% line impedance (1 100 HP @ 208 V, 1 - 250 HP @ 480 V)
- Displacement power factor of 0.98 throughout the motor speed range
- · NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (1 - 100 HP @ 208 V, 1 - 250 HP @ 480 V)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- · Differential PI feedback feature
- Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- Diagnostic fault indication
- · Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- Serial communication status

- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed
- BTL certified


#### Options

- Circuit Breaker (100 kAIC, additional fuses not required)
- Input Fuses
- 3-Contactor Bypass
- Drive Service Switch
- Two Motor "AND"Two Motor "OR"
- Output Reactor
- Input Reactor
- Noise Filter
- Custom Nameplate
- EtherNet/IP
- LonWorks
- Modbus TCP/IP

### **Model Number Configuration (Z1BB)**

**Step 1.** Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1BB)

#### **Enclosure Options**

NEMA 12

(B) The drive and Configured options are provided in a NEMA Type 12 (1) ventilated enclosure, large enough to accommodate any or all of the Configured package options.

### **Power Options**

Circuit Breaker

Motor Control (A, Y) Simultaneous control of two identical motors is possible with the 'AND' configuration, option (A). Either one of two motors can be controlled with the 'OR' configuration, option (Y).

(M) The standard configuration provides an input disconnect switch with a padlockable operator mechanism. This disconnect switch DOES NOT provide motor short circuit protection. If motor short circuit protection is desired in the bypass enclosure, select option (M), which provides a circuit breaker (100 kAIC) with a padlockable operator mechanism.

## Z1000 Bypass Drive NEMA Type 12 (Z1BB)

Input Fuses	(F)	Option (F) provides drive input fuses for increased drive input over current protection.
Drive Input Circuit	(B, G)	The standard configuration does not include any protection or disconnecting means specifically for the drive. For a 3-contactor bypass that removes power from the drive, select option (B). For an input disconnect switch that removes power from the drive, select option (G).
Input Reactor	(R)	The standard configuration does not provide any additional AC line impedance. Option (R) can be selected to add a 3% AC line input reactor.
Input Filter	(N)	The standard configuration for 125 to 150 HP $@$ 208V and for 300 to 500 HP $@$ 480V does not include a RFI filter. The cap filter, option (N), is a passive deltawye capacitive network.
Output Reactor	(K)	No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long leadlengths or noise reduction).
Control Option	S	
Ethernet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## **Model and Power Option Selection (Z1BB)**

### **208 V Models and Power Options**

						Legend: A =	Available	N/A = Not a	vailable or	not applica	ble	
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *1	NEMA 12 Bypass	Circuit Breaker (100 kAIC)	Input Fuses	3- Contactor Bypass	Drive Input Service Switch	Two Motor "AND"	Two Motor "OR"	Output Reactor	Input Reactor	Cap Filter
	(*po)		<b>Z1BB</b>	М	F	В	G	Α	Y	К	R	N
	2.4	0.5	D002									
	3.5	0.75	D003									
	4.6	1	D004	A	A	A	А	A	A		A	
	7.5	2	D007									
	10.6	3	D010									
	16.7	5	D016									
	24.2	7.5	D024									
	30.8	10	D030									
000.17	46.2	15	D046							А		N/A
208 V 3-Phase	59.4	20	D059									
0 1 1.000	74.8	25	D074									
	88	30	D088									
	114	40	D114									
	143	50	D143									
	169	60	D169				N/A					
	211	75	D211				IN/A					
	273	100	D273									
	343	125	D343									Α
	396	150	D396									_ ^

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full Load Current, Three-Phase Alternating Current Motors at 208 volts.

## Z1000 Bypass Drive NEMA Type 12 (Z1BB)

### **480 V Models and Power Options**

		:   HP *1		Legend: A = Available N/A = Not available or not applicable									
Rated Input Voltage	Rated Output Current (Amps)		NEMA 12 Bypass	Circuit Breaker (100 kAIC)	Input Fuses	3- Contactor Bypass	Drive Input Service Switch	Two Motor "AND"	Two Motor "OR"	Output Reactor	Input Reactor	Cap Filter	
	(*)		<b>Z1BB</b>	M	F	В	G	Α	Y	К	R	N	
	1.6	0.5 & 0.75	B001										
	2.1	1	B002										
	3.2	2	B003										
	4.8	3	B004										
	7.6	5	B007		A								
	11	7.5	B011	A									
	14	10	B014										
	21	15	B021				Α						
	27	20	B027			A		А					
	34	25	B034										
	40	30	B040									N/A	
	52	40	B52L										
480 V 3-Phase	52	40	B052						A	A	A		
0 1 1.000	65	50	B065										
	77	60	B077										
	96	75	B096										
	124	100	B124										
	156	125	B156										
	180	150	B180										
	240	200	B240				N/A						
	302	250	B302				IN/A						
	361	300	B361										
	414	350	B414									A	
	477	400	B477									_ ^	
	590	500	B590										

<sup>1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full Load Current, Three-Phase Alternating Current Motors at 480 volts.

## **Dimensions and Data (Z1BB)**

## **208 V NEMA Type 12**

Dated Z1B		Rated			Submittal		Enclo	Enclosed, NEMA 12 Bypass Data				
Rated Input	Bypass	Output	Nominal HP	Bypass	Documents (Outline Drawing)	Drive Part No	Overall Dimensions (in)			Weight		
Malkana	Base No. Z1BB□□□□ (Amps)			Box No.	(Schematic) (Submittal Guide)	CIMR-ZU	н	w	D	(lb)		
	D002	2.4	0.5			2A0011FAA						
	D003	3.5	0.75			2A0011FAA						
	D004	4.6	1	W1	DD.Z1BB.12.W1.01 DS.Z1B2.01*2	2A0011FAA	28.8	17.9	17.9	150		
	D007	7.5	2	VVI	SG.Z1B2.10	2A0011FAA	28.8	17.9	17.9	150		
	D010	10.6	3			2A0011FAA						
	D016	16.7	5			2A0017FAA						
	D024	24.2	7.5	WO	DD.Z1BB.12.W2.01 DS.Z1B2.01 <sup>*2</sup> SG.Z1B2.10	2A0024FAA	04.0	20.5	17.9	0.40		
	D030	30.8	10	W2		2A0031FAA	34.8			210		
	D046	46.2	15		DD.Z1BB.12.W3.01 DS.Z1B2.01 *2	2A0046FAA	39.8	25.5	17.3	275		
208 V 3-Phase	D059	59.4	20	W3		2A0059FAA						
0111000	D074	74.8	25		SG.Z1B2.10	2A0075FAA						
	D088	88	30		DD.Z1BB.12.W4.01	2A0088FAA			22.8	420		
	D114	114	40	W4	DS.Z1B2.01 *2 SG.Z1B2.10	2A0114FAA	51.2	32.7		490		
	D143	143	50			2A0143FAA				850		
	D169	169	60			2A0169FAA				945		
	D211	211	75	F1 *1	DD.Z1.12.F1.01 *1	2A0211FAA	04.0	44.0*1	20.0*1	945		
	D273	273	100	FI	DS.Z1B2.01*2 SG.Z1B2.10	2A0273FAA	84.2	41.3*1	32.0 *1	1,215		
	D343	343	125		00.2.220	2A0343UAA				1,300		
	D396	396	150			2A0396UAA				1,350		

<sup>\*1.</sup> Drive models D343, D396, B361, and B414 that have the "OR" or "AND" option refer to DD.Z1.12.F2.01

<sup>\*2.</sup> Drives that have "OR" option refer to DS.Z1B2.02; drives that have "AND" option refer to DS.Z1B2.03

## Z1000 Bypass Drive NEMA Type 12 (Z1BB)

### 480 V NEMA Type 12

	71B	Z1B Rated			Submittal		Enclos	ed, NEN	/A 12 By	pass Data
Rated Input	Bypass	Output	Nominal HP	Bypass	Documents (Outline Drawing)	Drive Part No	Overall	Dimens	ions (in)	Weight
Voltage	Base No. Z1BB□□□□	Current (Amps)		Box No.	(Schematic) (Submittal Guide)	CIMR-ZU	н	w	D	(lb)
	B001	1.6	0.75			4A0005FAA			17.9	
	B002	2.1	1			4A0005FAA		17.9		
	B003	3.4	2	W1	DD.Z1BB.12.W1.01 DS.Z1B2.01*2	4A0005FAA	28.8			150
	B004	4.8	3	VVI	SG.Z1B2.10	4A0005FAA	20.0	17.9	17.9	130
	B007	7.6	5			4A0008FAA				
	B011	11	7.5			4A0011FAA				
	B014	14	10		DD.Z1BB.12.W2.01	4A0014FAA		20.5	17.9	
	B021	21	15	W2	DS.Z1B2.01*2 SG.Z1B2.10	4A0021FAA	34.8			210
	B027	27	20			4A0027FAA				
	B034	34	25	W3	DD.Z1BB.12.W3.01 DS.Z1B2.01 <sup>'2</sup> SG.Z1B2.10	4A0034FAA	39.8			
	B040	40	30			4A0040FAA		25.5	17.3	275
	B52L	52	40			4A0052FAB		25.5		
480 V 3-Phase	B052	52	40			4A0052FAA				
J-Filase	B065	65	50		DD.Z1BB.12.W4.01 DS.Z1B2.01 <sup>12</sup> SG.Z1B2.10	4A0065FAA	51.2	32.7	22.8	410
	B077	77	60	W4		4A0077FAA				475
	B096	96	75	VV <del>4</del>		4A0096FAA				500
	B124	124	100			4A0124FAA				550
	B156	156	125			4A0156FAA				850
	B180	180	150			4A0180FAA				950
	B240	240	200	F1 *1	DD.Z1.12.F1.01 *1	4A0240FAA	84.2	41.3*1	32.0 *1	950
	B302	302	250	FI '	DS.Z1B2.01 *2 SG.Z1B2.10	4A0302FAA	04.2	41.5	32.0	1,200
	B361	361	300			4A0361UAA				1,300
	B414	414	350			4A0414UAA	1			1,315
	B477	477	400		DD.Z1.12.F2.01	4A0477UAA				1,900
	B590	590	500	F2	DS.Z1B2.01*2 SG.Z1B2.10	4A0590UAA	84.2	69.8	30.5	2,100

<sup>\*1.</sup> Drive models B361, and B414 that have the "OR" or "AND" option refer to DD.Z1.12.F2.01

<sup>\*2.</sup> Drives that have "OR" option refer to DS.Z1B2.02; drives that have "AND" option refer to DS.Z1B2.03

## Bypass Drive NEMA Type 3R (Z1B3)

### Specifications: 208 and 480 V NEMA Type 3R (Z1B3)



The Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control.

The bypass package provides a Z1000 drive in a NEMA 3R (UL Type 3R) enclosure and lockable main input circuit breaker with a 3contactor style bypass to allow motor operation from the drive or across the line.

The bypass features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 1 to150 HP, 208 Vac 1 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150%
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- · Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - **Customer Safeties**
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque

#### **Bypass Features**

- · Bypass and Drive output contactors
- · 3-Contactor Bypass
- · Thermal motor overload relay, class 20
- · 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- · Selectable energy savings and harmonic reduction mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- · Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 3R (IP14): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C  $\,$  LCD keypad: Hand-Off-Auto functions (-4 °F to 158 °F)
- Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Built in 5% line impedance (1 100 HP @ 208 V, 1 - 250 HP @ 480 V)
- Displacement power factor of 0.98 throughout the motor speed range
- · NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (1 - 100 HP @ 208 V, 1 - 250 HP @ 480 V)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- Diagnostic fault indication
- Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- Serial communication status

- · Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- · UL, cUL listed
- · BTL certified

#### **Options**


- Input Fuses
- Two Motor "AND"
- Two Motor "OR"
- Output Reactor Input Reactor
- Input Filter
- Surge Suppressor
- Space Heater
- Custom Nameplate
- EtherNet/IP LonWorks
- · Keypad Viewing Window

## Bypass Drive NEMA Type 3R (Z1B3)

### **Model Number Configuration (Z1B3)**

**Step 1.** Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



## Options (Z1B3)

### **Enclosure Options**

NEMA 3R	(3)	The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.
Freestanding Leg Kit NEMA 3R	UUX000923	<b>12 in. Leg Kit:</b> This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.
	UUX000924	<b>30 in. Leg Kit:</b> This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.

## **Power Options**

Motor Control	(A, Y)	Simultaneous control of two identical motors is possible with the 'AND' configuration, option (A). Either one of two motors can be controlled with the 'OR' configuration, option (Y).
Input Fuses	(F)	Option (F) provides drive input fuses for increased drive input over current protection.
Output Reactor	(K)	No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long leadlengths or noise reduction).
Input Reactor	(R)	The standard configuration does not provide any additional AC line impedance. Option (R) can be selected to add a 3% AC line input reactor.
Input Filter	(N)	The standard configuration for 125 to 150 HP @ 208V and for 300 to 500 HP @ 480V does not include a RFI filter. The cap filter, option (N), is a passive deltawye capacitive network.
Surge Suppressor	(2)	This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.
Space Heater	(3)	This option helps reduce condensation.
Control Options		
Ethernet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Keypad Viewing Window	(M)	The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## Bypass Drive NEMA Type 3R (Z1B3)

## **Model and Power Option Selection (Z1B3)**

### **208 V Models and Power Options**

			NEMA 3R		Lege	nd: A = Avail	able N/A =	Not available	or not ap	pplicable	
Rated Input	Rated Output Current	Nominal	Bypass Bypass	Input Fuses	Two Motor "AND"	Two Motor "OR"	Output Reactor	Input Reactor	Cap Filter	Surge Suppressor	Space Heater
Voltage	(Amps)		<b>Z1B3</b> □□□□	F	Α	Y	к	R	N	2	3
	2.4	0.5	D002								
	3.5	0.75	D003								
	4.6	1	D004								
	7.5	2	D007		A	A	A	A	N/A	A	
	10.6	3	D010								
	16.7	5	D016								
	24.2	7.5	D024								
	30.8	10	D030								
00011	46.2	15	D046								
208 V 3-Phase	59.4	20	D059	Α							Α
	74.8	25	D074								
	88	30	D088								
	114	40	D114								
	143	50	D143								
	169	60	D169								
	211	75	D211								
	273	100	D273								
	343	125	D343						Α		
	396	150	D396						τ.		

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

			NEMA 3R		Lege	end: A = Avai	ilable N/A =	Not availab	le or not a	oplicable	
Rated Input Voltage	Rated Output Current	Nominal HP *1	Bypass Bypass	Input Fuses	Two Motor "AND"	Two Motor "OR"	Output Reactor	Input Reactor	Cap Filter	Surge Suppressor	Space Heater
voltage	(Amps)		<b>Z1B3</b> □□□□	F	Α	Y	к	R	N	2	3
	1.6	0.5 & 0.75	B001								
	2.1	1	B002								
	3.2	2	B003								
	4.8	3	B004								
	7.6	5	B007								
	11	7.5	B011								
	14	10	B014								
	21	15	B021								
	27	20	B027								
	34	25	B034								
	40	30	B040						N/A		
	52	40	B52L								
480 V 3-Phase	52	40	B052	Α	Α	Α	Α	Α		A	Α
o i nasc	65	50	B065								
	77	60	B077								
	96	75	B096								
	124	100	B124								
	156	125	B156								
	180	150	B180								
	240	200	B240								
	302	250	B302								
	361	300	B361								
	414	350	B414								
	477	400	B477						Α		
	590	500	B590								

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

# Bypass Drive NEMA Type 3R (Z1B3)

## **Dimensions and Data (Z1B3)**

### 208 V NEMA Type 3R

	Z1B	Rated			Submittal		Enclos	ed, NEN	IA 3R By	pass Data
Rated Input	Bypass Base No.	Output	Nominal HP	Bypass Box No.	Documents (Outline Drawing)	Drive Part No	Overall	Dimens	ions (in)	Weight
Voltage	<b>Z1B3</b> □□□□	Current (Amps)		Box No.	(Schematic) (Submittal Guide)	CIMR-ZU	н	w	D	(lb)
	D002	2.4	0.5			2A0011FAA				
	D003	3.5	0.75			2A0011FAA				
	D004	4.6	1	W1	DD.Z1.3R.W1.01 DS.Z1B3.01*2	2A0011FAA	29.1	21.2	21.4	150
	D007	7.5	2	VVI	SG.Z1B3.10	2A0011FAA	29.1	21.2	21.4	150
	D010	10.6	3			2A0011FAA				
	D016	16.7	5			2A0017FAA				
	D024	24.2	7.5	14/0	DD.Z1.3R.W2.01	2A0024FAA	04.0	00.7	04.4	040
	D030	30.8	10	W2	DS.Z1B3.01*2 SG.Z1B3.10	2A0031FAA	34.8	23.7	21.4	210
	D046	46.2	15		DD.Z1.3R.W3.01	2A0046FAA				
208 V 3-Phase	D059	59.4	20	W3	DS.Z1B3.01 *2	2A0059FAA	40.1	28.7	21.4	275
3-Filase	D074	74.8	25		SG.Z1B3.10	2A0075FAA				
	D088	88	30	10/4	DD.Z1.3R.W4.01	2A0088FAA	F4.4	00.0	04.4	420
	D114	114	40	W4	DS.Z1B3.02*2 SG.Z1B3.10	2A0114FAA	51.1	39.0	21.4	490
	D143	143	50			2A0143AAA				850
	D169	169	60		DD.Z1.3R.F1.01 DS.Z1B3.02 *2	2A0169AAA		41.3	50.7	945
	D211	211	75	<b>-</b> . *1	SG.Z1B3.10	2A0211AAA	]	41.3	50.7	945
	D273	273	100	F1 *1		2A0273AAA	91.1			1,215
	D343	343	125		DD.Z1.3R.F1.03 *1	2A0343AAA		44.0*4	40.0*1	1,300
	D396	396	150		DS.Z1B3.02 *2 SG.Z1B3.10	2A0396AAA		41.3*1	46.6*1	1,350

<sup>\*1.</sup> Drive models D343 and D396 that have the "OR" or "AND" option refer to DD.Z1.3R.F2.01

<sup>\*2.</sup> Drives that have "OR" option refer to DS.Z1B3.09/10/12, drives that have "AND" option refer to DS.Z1B3.05/06/08

### 480 V NEMA Type 3R

	_Z1B	Rated			Submittal		Enclos	ed, NEN	IA 3R By	pass Data
Rated Input	Bypass Base No.	Output	Nominal HP	Bypass	Documents (Outline Drawing)	Drive Part No	Overall	Dimensi	ions (in)	Weight
Voltage	<b>Z1B3</b> □□□□	Current (Amps)		Box No.	(Schematic) (Submittal Guide)	CIMR-ZU	н	w	D	(lb)
	B001	1.6	0.75			4A0005FAA				
	B002	2.1	1			4A0005FAA				
	B003	3.4	2	W1	DD.Z1.3R.W1.01 DS.Z1B3.01*2	4A0005FAA	29.1	21.2	21.4	150
	B004	4.8	3	VVI	SG.Z1B3.10	4A0005FAA	29.1	21.2	21.4	150
	B007	7.6	5			4A0008FAA				
	B011	11	7.5			4A0011FAA				
	B014	14	10		DD.Z1.3R.W2.01	4A0014FAA				
	B021	21	15	W2	DS.Z1B3.01 *2	4A0021FAA	34.8	23.7	21.4	210
	B027	27	20		SG.Z1B3.10	4A0027FAA				
	B034	34	25			4A0034FAA				
	B040	40	30	W3	DD.Z1.3R.W3.01 DS.Z1B3.01*2	4A0040FAA	40.1	20.7	21.4	275
	B52L	52	40	VVS	SG.Z1B3.10	4A0052FAB	40.1	28.7		213
	B052	52	40			4A0052FAA				
480 V	B065	65	50			4A0065FAA				410
3-Phase	B077	77	60	W4	DD.Z1.3R.W4.01 DS.Z1B3.02*2	4A0077FAA	51.1	39.0	21.4	475
	B096	96	75	VV <del>4</del>	SG.Z1B3.10	4A0096FAA	31.1	39.0		500
	B124	124	100			4A0124AAA				550
	B156	156	125			4A0156AAA				850
	B180	180	150		DD.Z1.3R.F1.01	4A0180AAA		41.3	50.7	950
	B240	240	200		SG.Z1B3.10	4A0240AAA		41.3	30.7	950
	B302	302	250			4A0302AAA				1,200
	B361	361	300	F1 *1	DD.Z1.3R.F1.03 *1 DS.Z1B3.02 *2 SG.Z1B3.10	4A0361AAA	91.1	44.0*1	40.0*1	1,300
	B414	414	350		DD.Z1.3R.F1.03 *1 DS.Z1B3.03 *2 SG.Z1B3.10	4A0414AAA		41.3	46.6	1,315
	B477	477	400		DD.Z1.3R.F2.01	4A0480AAA				1,900
	B590	590	500	F2	F2 DS.Z1B3.04 *2	4A0590AAA	91.1	66.3	43.5	2,100
	B302 B361 B414 B477	302 361 414 477	250 300 350 400	F1 '1 F2	DD.Z1.3R.F1.03 <sup>11</sup> DS.Z1B3.02 <sup>12</sup> SG.Z1B3.10  DD.Z1.3R.F1.03 <sup>11</sup> DS.Z1B3.03 <sup>12</sup> SG.Z1B3.10  DD.Z1.3R.F2.01	4A0302AAA 4A0361AAA 4A0414AAA 4A0480AAA	91.1	41.3*1	46.6 <sup>*1</sup>	1,; 1,; 1,;

<sup>\*1.</sup> Drive models B361 and B414 that have the "OR" or "AND" option refer to DD.Z1.3R.F2.01

<sup>\*2.</sup> Drives that have "OR" option refer to DS.Z1B3.09/10/12, drives that have "AND" option refer to DS.Z1B3.05/06/08

## Z1000 Configured Drive NEMA Type 1 (Z1C1)

### Specifications: 208 and 480 V NEMA Type 1 (Z1C1)



The Z1000 Configured package provides a Z1000 in a NEMA 1 enclosure, with input disconnect switch and space for several commonly used option, such as reactors, fuses, circuit breakers, etc. The Z1000 Configured has been designed for flexibility in providing the features and options commonly specified by facility designers.

The Z1000 Drive is a variable torque AC drive, designed specifically for HVAC applications in building automation. A new benchmark for size, cost, performance, benefits, and quality, the Z1000 includes numerous built-in features such as Network Communications, H/O/A, PI control, and energy-savings functions.

The Z1000 has embedded communications for the popular building automation protocols BACnet, Modbus, Siemens APOGEE, and Johnson Controls Metasys. Optional LonWorks or EtherNet/IP interface cards are also available.

#### **Performance Features**

- VT Ratings: 1 to 150 HP, 208 Vac 1 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Motor preheat function
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Power loss ride through: 2 seconds
- Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection
- Up/down floating point control capability
- Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command)
  - 0 to 10 Vdc (20 K Ohm)
  - 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### Service Conditions

- · Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by
- · Service factor: 1.0

#### **Design Features**

- Lockable main input disconnect switch
- Built in 5% line impedance (1 to 100 HP @ 208V, 3 to 250 HP @ 480V)
- Displacement power factor of 0.98 throughout Customizable monitor display the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (1 to 100 HP @ 208V, 3 to 250 HP @ 480V)
- · Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- · Two internal (PI) Controls
- · Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- · Differential PI feedback feature
- Sleep function in both closed loop and open loop control
- Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- · VFD efficiency: 98% at full-speed; 96% at half-
- · Diagnostic fault indication
- · "S-curve" soft start / soft stop capability

- Serial communication loss detection and selectable response strategy
- Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 2 amps @ 250 Vac & 30 Vdc)
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions with a built-in copy feature
- Motor preheat function
- Flash upgradeable firmware
- Heat sink over temperature speed foldback
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL. cUL listed
- BTL listed
- IBC 2012


#### Options

- · Circuit Breaker (65 kAIC or 100 kAIC)
- · Input Fuses
- Input Reactor
- Input Filter
- Custom Nameplate
- EtherNet/IP
- LonWorks

### **Model Number Configuration (Z1C1)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1C1)

### **Enclosure Options**

NEMA 1

(1) The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

# Z1000 Configured Drive NEMA Type 1 (Z1C1)

### **Power Options**

Circuit Breaker	(C, M)	The standard configuration provides a line input disconnect switch but no branch short circuit protection. Circuit breaker options are available. Option (C) is a 65 kAIC rated circuit breaker and option (M) is a 100 kAIC rated circuit breaker. When option (C) is specified, the configured drive package will be rated at 65 kAIC. When option (M) is specified, the configured drive package will be rated at 100 kAIC.
Input Fuses	(F)	Option (F) provides drive input fuses for increased drive input over current protection.
Input Reactor	(R)	The standard configuration does not provide any additional AC line impedance.  Option (R) can be selected to add a 3% AC line input reactor.  Note: Consult factory for availability on certain models. Certain capacities will not accommodate the R option.
Input Filter	(N)	The standard configuration for 125 to 150 HP $@$ 208V and for 300 to 500 HP $@$ 480V does not include a RFI filter. The cap filter, option (N), is a passive deltawye capacitive network.
Control Options	5	
EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## **Model and Power Option Selection (Z1C1)**

					Legend: A	A = Available	N/A = Not av	ailable or not a	applicable
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *1	NEMA 1 Configured	Typical Lead Time	Circuit Breaker (65 kAIC)	Circuit Breaker (100 kAIC)	Input Fuse	Input Reactor 3%	Noise Filter
			<b>Z1C1</b> □□□□		С	М	F	R	N
	2.4	0.5	D002						
	3.5	0.75	D003						
	4.6	1	D004						
	7.5	2	D007						
	10.6	3	D010					Α	
	16.7	5	D016						
	24.2	7.5	D024						
	30.8	10	D030	10 Working Days					
	46.2	15	D046	Days					N/A
208 V 3-Phase	59.4	20	D059		Α	Α	Α		
o i nasc	74.8	25	D074					N1/A	
	88	30	D088					N/A	
	114	40	D114						
	143	50	D143						1
	169	60	D169						
	211	75	D211						
-	273	100	D273					A	
	343	125	D343	_					^
	396	150	D396						A

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

# Z1000 Configured Drive NEMA Type 1 (Z1C1)

					Legend: A	A = Available	N/A = Not av	ailable or not a	applicable
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *1	NEMA 1 Configured	Typical Lead Time	Circuit Breaker (65 kAIC)	Circuit Breaker (100 kAIC)	Input Fuse	Input Reactor 3%	Noise Filter
			Z1C1		С	М	F	R	N
	1.6	0.5 & 0.75	B001						
	2.1	1	B002						
	3.2	2	B003						
	4.8	3	B004						
	7.6	5	B007						
	11	7.5	B011						
	14	10	B014						
	21	15	B021						
	27	20	B027	10.10/2 - 15:					
	34	25	B034	10 Working Days					
	40	30	B040						N/A
400.17	52	40	B52L						
480 V 3-Phase	52	40	B052		Α	Α	Α	Α	
	65	50	B065						
	77	60	B077						
	96	75	B096						
	124	100	B124						
	156	125	B156						
	180	150	B180						
	240	200	B240						
	302	250	B302						
	361	300	B361	_					
	414	350	B414	_					A
	477	400	B477						_ ^
	590	500	B590						

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

## **Dimensions and Data (Z1C1)**

## 208 V NEMA Type 1

		Rated			Submittal Documents			Enclose	ed, NEM	<b>A</b> 1
Rated Input Voltage	Z1C Configured Base No. Z1C1	Output Current	Nominal HP	Configured Box No.	(Outline Drawing) (Schematic)	Drive Part No. CIMR-ZU	Overa	II Dimer (in)	sions	Weight (lb)
		(Amps)			(Submittal Guide)		Н	W	D	(ID)
	D002	2.4	0.5			2A0011FAA	41.60	6.77	12.92	65
	D003	3.5	0.75			2A0011FAA	41.60	6.77	12.92	65
	D004	4.6	1	W1	DD.Z1C1.W1.01 DS.Z1C1.01	2A0011FAA	41.60	6.77	12.92	65
	D007	7.5	2	VVI	SG.Z1C1.01	2A0011FAA	41.60	6.77	12.92	65
	D010	10.6	3			2A0011FAA	41.60	6.77	12.92	65
	D016	16.7	5			2A0017FAA	41.60	6.77	12.92	65
	D024	24.2	7.5	1440	DD.Z1C1.W2.01	2A0024FAA	45.10	6.77	12.92	75
	D030	30.8	10	W2	DS.Z1C1.01 SG.Z1C1.10	2A0031FAA	45.10	6.77	12.92	75
	D046	46.2	15		DD.Z1C1.W3.01	2A0046FAA	48.20	10.18	13.19	85
208 V 3-Phase	D059	59.4	20	W3	DS.Z1C1.01 SG.Z1C1.10	2A0059FAA	48.20	10.18	13.19	85
	D074	74.8	25		DD.Z1C1.W4.01	2A0075FAA	52.80	12.68	14.20	150
	D088	88	30	W4	DS.Z1C1.01	2A0088FAA	52.80	12.68	14.20	155
	D114	114	40		SG.Z1C1.10	2A0114FAA	52.80	12.68	14.20	160
	D143	143	50			2A0143FAA	49.09	28.41	20.87	360
	D169	169	60	W6	DD.Z1C1.W6.01 DS.Z1C1.01	2A0169FAA	49.09	28.41	20.87	370
	D211	211	75	7 70	SG.Z1C1.01 SG.Z1C1.10	2A0211FAA	49.09	28.41	20.87	385
	D273	273	100			2A0273FAA	49.09	28.41	20.87	450
	D343	343	125	F.4	DD.Z1.1.F1.02	2A0343AAA	04.00	44.50	0.4.00	1,150
	D396	396	150	F1	DS.Z1C1.02 SG.Z1C1.10	2A0396AAA	FAA 41.60 6 FAA 45.10 6 FAA 45.10 6 FAA 48.20 1 FAA 48.20 1 FAA 52.80 1 FAA 52.80 1 FAA 52.80 1 FAA 49.09 2	41.50	34.00	1,300

# Z1000 Configured Drive NEMA Type 1 (Z1C1)

## 480 V NEMA Type 1

		Rated			Submittal Documents			Enclose	ed, NEM	A 1
Rated Input Voltage	Z1C Configured Base No. Z1C1	Output Current	Nominal HP	Configured Box No.	(Outline Drawing) (Schematic)	Drive Part No. CIMR-ZU	Overa	II Dimer (in)	sions	Weight
Voltage		(Amps)			(Submittal Guide)		Н	W	D	(lb)
	B001	1.1	0.5			4A0005FAA	41.60	6.77	12.92	65
	B001	1.6	0.75			4A0005FAA	41.60	6.77	12.92	65
	B002	2.1	1		DD.Z1C1.W1.01	4A0005FAA	41.60	6.77	12.92	65
	B003	3.4	2	W1	DS.Z1C1.01	4A0005FAA	41.60	6.77	12.92	65
	B004	4.8	3		SG.Z1C1.10	4A0005FAA	41.60	6.77	12.92	65
	B007	7.6	5			4A0008FAA	41.60	6.77	12.92	65
	B011	11	7.5			4A0011FAA	41.60	6.77	12.92	65
	B014	14	10		DD.Z1C1.W2.01	4A0014FAA	45.10	6.77	12.92	75
	B021	21	15	W2	DS.Z1C1.01	4A0021FAA	45.10	6.77	12.92	75
	B027	27	20		SG.Z1C1.10	4A0027FAA	45.10	6.77	12.92	75
	B034	34	25		DD.Z1C1.W3.01	4A0034FAA	48.20	10.18	13.19	85
	B040	40	30	W3	DS.Z1C1.01	4A0040FAA	48.20	10.18	13.19	85
	B52L	52	40		SG.Z1C1.10	4A0052FAB	48.20	10.18	13.19	85
480 V	B052	52	40			4A0052FAA	52.80	12.68	14.20	150
3-Phase	B065	65	50	W4	DD.Z1C1.W4.01 DS.Z1C1.01	4A0065FAA	52.80	12.68	14.20	155
	B077	77	60		SG.Z1C1.10	4A0077FAA	52.80	12.68	14.20	160
	B096	96	75			4A0096FAA	52.80	12.68	14.20	180
	B124	124	100	W5	DD.Z1C1.W5.01 DS.Z1C1.01 SG.Z1C1.10	4A0124FAA	42.79	25.80	16.06	240
	B156	156	125		DD.Z1C1.W6.01	4A0156FAA	49.09	28.41	20.87	355
	B180	180	150	W6	DS.Z1C1.01	4A0180FAA	49.09	28.41	20.87	385
	B240	240	200		SG.Z1C1.10	4A0240FAA	49.09	28.41	20.87	450
	B302	302	250		DD.Z1.1.F1.01	4A0302FAA				1,150
	B361	361	300	F1	DS.Z1C1.02	4A0361AAA	84.00	42.00	34.00	1,300
	B414	414	350		SG.Z1C1.10	4A0414AAA				1,400
	B477	477	400		DD.Z1.1.F1.04	4A0477AAA	00.00	44.50	00.00	1,500
	B590	590	500	F1T	DS.Z1C1.02 SG.Z1C1.10	4A0590AAA	92.00	41.50	32.00	1,600

# Configured Drive NEMA Type 12 (Z1CB)

### Specifications: 208 and 480 V NEMA Type 12 (Z1CB)



The Z1000 NEMA 12 Configured drive is engineered to allow flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input disconnect switch and space for several power options inside a NEMA 12 (UL Type 12) enclosure.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 1 to 150 HP, 208 Vac 1 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% 24 Vdc, 150 ma transmitter power supply
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Motor preheat function
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Power loss ride through: 2 seconds
- Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection
- Up/down floating point control capability
- · Stationary motor auto-tuning

#### **Design Features**

- · Lockable main input disconnect switch
- Built in 5% line impedance (1 to 100 HP @ 208V, 1 to 250 HP @ 480V)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (1 to 100 HP @ 208V, 3 to 250 HP @ 480V)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PI) Controls
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external
- Differential PI feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter

- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- · Input and output terminal status indication
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - **Customer Safeties**
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- Diagnostic fault indication
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 2 amps @ 250 Vac & 30 Vdc)
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions with a built-in copy feature
- Motor preheat function
- · Flash upgradeable firmware
- · Customizable monitor display

- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### **Service Conditions**

- · Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating
- · Service factor: 1.0

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- FN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed; CE marked
- BTL listed
- IBC-2012

#### Options


- Circuit Breaker (65 kAIC or 100 kAIC)
- · Input Fuses
- Two Motor "AND"
- Two Motor "OR"
- Output Reactor
- Input Reactor Input Filter
- · Custom Nameplate
- EtherNet/IP
  - LonWorks

# Configured Drive NEMA Type 12 (Z1CB)

### **Model Number Configuration (Z1CB)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### **Options (Z1CB)**

### **Enclosure Options**

NEMA 12

(B) The drive and Configured options are provided in a NEMA Type 12 (1) ventilated enclosure, large enough to accommodate any or all of the Configured package options.

## **Power Options**

Motor Control	(A, Y)	Simultaneous control of two identical motors is possible with the 'AND' configuration, option (A). Either one of two motors can be controlled with the 'OR' configuration, option (Y).
Circuit Breaker	(C, M)	The standard configuration provides a line input disconnect switch but no branch short circuit protection. Circuit breaker options are available. Option (C) is a 65 kAIC rated circuit breaker and option (M) is a 100 kAIC rated circuit breaker. When option (C) is specified, the configured drive package will be rated at 65 kAIC. When option (M) is specified, the configured drive package will be rated at 100 kAIC.
Input Fuses	(F)	Option (F) provides drive input fuses for increased drive input over current protection.
Output Reactor	(K)	No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long lead-lengths or noise reduction).
Input Reactor	(R)	The standard configuration does not provide any additional AC line impedance. Option (R) can be selected to add a 3% AC line input reactor.
Input Filter	(N)	The standard configuration for 125 to 150 HP $@$ 208V and for 300 to 500 HP $@$ 480V does not include a RFI filter. The cap filter, option (N), is a passive deltawye capacitive network.

# Configured Drive NEMA Type 12 (Z1CB)

### **Control Options**

EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
200 VA Transformer (CPT)	(K)	200 VA Control Power Transformer (for customer use).
Speed pot	(Z)	Door mounted.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## Model and Power Option Selection (Z1CB)

			NEMA 42		Lege	nd: A = Avail	able N/A =	Not available	or not appli	icable	
Rated Input Voltage	Rated Output Current	Nominal HP *1	NEMA 12 Configure d	Circuit Breaker (65 kAIC)	Circuit Breaker (100 kAIC)	Input Fuse	Two Motor "AND"	Two Motor "OR"	Load Reactor	Input Reactor	Noise Filter
	(Amps)		Z1CB □□□□	С	М	F	A	Y	к	R	N
	2.4	0.5	D002								
	3.5	0.75	D003								
	4.6	1	D004								
	7.5	2	D007								
	10.6	3	D010								
	16.7	5	D016								
	24.2	7.5	D024								
	30.8	10	D030								
000.17	46.2	15	D046								N/A
208 V 3-Phase	59.4	20	D059	Α	Α	Α	Α	Α	Α	Α	
0 1 11000	74.8	25	D074								
	88	30	D088								
	114	40	D114								
	143	50	D143								
	169	60	D169								
	211	75	D211								
	273	100	D273								
	343	125	D343								А
	396	150	D396								^

<sup>1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

			NEMA 12		Legei	nd: A = Avail	able N/A =	Not available	or not appl	icable	
Rated Input Voltage	Rated Output Current	Nominal HP	Configur	Circuit Breaker (65 kAIC)	Circuit Breaker (100 kAIC)	Input Fuse	Two Motor "AND"	Two Motor "OR"	Load Reactor	Input Reactor	Noise Filter
<b>-</b> -	(Amps)		Z1CB	С	М	F	Α	Y	К	R	N
	1.6	0.5 & 0.75	B001								
	2.1	1	B002								
	3.2	2	B003								
	4.8	3	B004								
	7.6	5	B007								
	11	7.5	B011								
	14	10	B014								
	21	15	B021								
	27	20	B027								
	34	25	B034								
	40	30	B040								N/A
	52	40	B52L								
480 V 3-Phase	52	40	B052	Α	Α	Α	A	Α	Α	Α	
	65	50	B065								
	77	60	B077								
	96	75	B096								
	124	100	B124								
	156	125	B156								
	180	150	B180								
	240	200	B240								
	302	250	B302								
	361	300	B361								
	414	350	B414								^
	477	400	B477								Α
	590	500	B590								

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

# Configured Drive NEMA Type 12 (Z1CB)

## **Dimensions and Data (Z1CB)**

## **208 V NEMA Type 12**

		Rated					i	Enclose	d, NEMA	\ 12
Rated Input Voltage	Z1C Configured Base No. Z1CB□□□□	Output Current	Nominal HP	Configured Box No.	Submittal Documents (Outline Drawing) (Schematic)	Drive Part No. CIMR-ZU	Overa	II Dimer (in)	sions	Weight
3393		(Amps)			(55)		Н	W	D	(lb)
	D002	2.4	0.5			2A0011FAA				
	D003	3.5	0.75			2A0011FAA				
	D004	4.6	1	W1	DD.Z1CB.12.W1.01	2A0011FAA	29.00	18.00	18.00	140
	D007	7.5	2	VV 1	DS.Z1C2.01	2A0011FAA	29.00	18.00	10.00	140
	D010	10.6	3			2A0011FAA				
	D016	16.7	5			2A0017FAA				
	D024	24.2	7.5	W2	DD.Z1CB.12.W2.01	2A0024FAA	35.00	20.50	18.00	200
	D030	30.8	10		DS.Z1C2.01	2A0031FAA	33.00	20.50	16.00	200
0001/	D046	46.2	15		DD.Z1CB.12.W3.01 DS.Z1C2.01	2A0046FAA				
208 V 3-Phase	D059	59.4	20	W3		2A0059FAA	40.00	25.50	17.50	260
0 1 11.000	D074	74.8	25			2A0075FAA				
	D088	88	30	W4	DD.Z1CB.12.W4.01	2A0088FAA	51.00	33.00	23.00	395
	D114	114	40	VV4	DS.Z1C2.01	2A0114FAA	31.00	33.00	23.00	465
	D143	143	50			2A0143FAA				800
	D169	169	60			2A0169FAA				910
	D211	211	75		DD.Z1.12.F1.01	2A0211FAA	84.00	41.50	34.00	910
	D273	273	100	-  F1 -	DS.Z1C2.01	2A0273FAA	04.00	41.50	34.00	1,150
	D343	343	125			2A0343AAA				1,200
	D396	396	150			2A0396AAA				1,250

## **480 V NEMA Type 12**

		Rated					ı	Enclose	d, NEMA	<b>1</b> 2
Rated Input Voltage	Z1C Configured Base No. Z1CB□□□□	Output Current	Nominal HP	Configured Box No.	Submittal Documents (Outline Drawing) (Schematic)	Drive Part No. CIMR-ZU	Overa	II Dimer (in)	nsions	Weight (lb)
		(Amps)			(		Н	W	D	(ID)
	B001	1.1	0.5			4A0005FAA				
	B001	1.6	0.75			4A0005FAA				
	B002	2.1	1			4A0005FAA				
	B003	3.4	2	W1	DD.Z1CB.12.W1.01 DS.Z1C2.01	4A0005FAA	29.00	18.00	18.00	140
	B004	4.8	3		50.2102.01	4A0005FAA				
	B007	7.6	5			4A0008FAA	1			
	B011	11	7.5			4A0011FAA				
	B014	14	10			4A0014FAA				
	B021	21	15	W2	DD.Z1CB.12.W2.01 DS.Z1C2.01	4A0021FAA	35.00	20.50	18.00	200
	B027	27	20		50.2102.01	4A0027FAA				
	B034	34	25		DD.Z1CB.12.W3.01 DS.Z1C2.01	4A0034FAA				260
	B040	40	30	W3		4A0040FAA				
480 V	B52L	52	40			4A0052FAB	40.00	25.50	17.50	
3-Phase	B052	52	40		50.2102.01	4A0052FAA				
	B065	65	50			4A0065FAA				
	B077	77	60			4A0077FAA				435
	B096	96	75	W4	DD.Z1CB.12.W4.01 DS.Z1C2.01	4A0096FAA	51.00	33.00	23.00	465
	B124	124	100		50.2102.01	4A0124FAA				505
	B156	156	125			4A0156FAA				795
	B180	180	150			4A0180FAA				895
	B240	240	200	F1	DD.Z1.12.F1.01	4A0240FAA	04.00	44.50	20.50	895
	B302	302	250	"	DS.Z1C2.01	4A0302FAA	84.00	41.50	32.50	1,100
	B361	361	300			4A0361AAA				1,200
	B414	414	350			4A0414AAA				1,250
	B477	477	400	F4T	DD.Z1.12.F1.02	4A0477AAA	00.00	44.50	22.00	1,500
	B590	590	500	F1T	DS.Z1C2.01	4A0590AAA	92.00	41.50	32.00	1,600

# Configured Drive NEMA Type 3R (Z1C3)

### Specifications: 208 and 480 V NEMA Type 3R (Z1C3)



The Z1000 NEMA 3R Configured drive is engineered to allow flexibility when providing the features and options commonly specified by facility designers

The configured package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input disconnect switch and space for several power options inside a NEMA 3R (UL Type 3R) enclosure.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 1 to 150 HP, 208 Vac 1 to 500 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150%
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Motor preheat function
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- Power loss ride through: 2 seconds
- Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection
- Up/down floating point control capability
- · Stationary motor auto-tuning

### **Design Features**

- · Lockable main input disconnect switch
- Built in 5% line impedance (1 to 100 HP @ 208V, 1 to 250 HP @ 480V)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2) (1 to 100 HP @ 208V, 1- 250 HP @ 480V)
- · Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PI) Controls
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- Sleep function in both closed loop and open loop control
- Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply

- 140% starting torque capability, available from Service Conditions 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
- 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5
- · Programmable security code
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - **Customer Safeties**
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- Input and output terminal status indication
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- Diagnostic fault indication
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status
- · No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 2 amps @ 250 Vac & 30 Vdc)
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions with a built-in copy feature
- · Motor preheat function
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- · Fan failure detection and selectable drive action

- 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 3R: -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by
- · Service factor: 1.0

#### **Standards**


- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- · UL, cUL listed; CE marked
- BTL listed

- · Circuit Breaker (65 kAIC or 100 kAIC)
- Input Fuses
- Two Motor "AND"
- Two Motor "OR"
- Output Reactor
- · Input Reactor
- · Input Filter
- Surge Suppressor
- Space Heater
- · Custom Nameplate
- EtherNet/IP
- LonWorks
- · Keypad Viewing Window

## **Model Number Configuration (Z1C3)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



# Configured Drive NEMA Type 3R (Z1C3)

## Options (Z1C3)

## **Enclosure Options**

NEMA 3R	(3)	The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.
Freestanding Leg Kit NEMA 3R	UUX000923	<b>12 in. Leg Kit:</b> This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.
	UUX000924	<b>30 in. Leg Kit:</b> This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.

### **Power Options**

<u> </u>		
Motor Control	(A, Y)	Simultaneous control of two identical motors is possible with the 'AND' configuration, option (A). Either one of two motors can be controlled with the 'OR' configuration, option (Y).
Circuit Breaker	(C, M)	The standard configuration provides a line input disconnect switch but no branch short circuit protection. Circuit breaker options are available. Option (C) is a 65 kAIC rated circuit breaker and option (M) is a 100 kAIC rated circuit breaker. When option (C) is specified, the configured drive package will be rated at 65 kAIC. When option (M) is specified, the configured drive package will be rated at 100 kAIC.
Input Fuses	(F)	Option (F) provides drive input fuses for increased drive input over current protection.
Output Reactor	(K)	No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long lead-lengths or noise reduction).
Input Reactor	(R)	The standard configuration does not provide any additional AC line impedance. Option (R) can be selected to add a 3% AC line input reactor.

Input Filter	(N)	480V do	dard configuration for 125 to 150 HP @ 208V and for 300 to 500 HP @ es not include a RFI filter. The cap filter, option (N), is a passive delta-acitive network.					
Surge Suppressor	(2)	•	s option provides a degree of protection from transient surges coming ough the power line cables. Lightning strikes are the most common source of ges.					
Space Heater	(3)	This opt	cion helps reduce condensation.					
<b>Control Options</b>								
EtherNet/IP SI-EN3		(D)	EtherNet/IP, option (D), requires the addition of an optional board.					
LonWorks SI-W3		(L)	LonWorks, option (L), requires the addition of an optional board.					
Keypad Viewing Win	ndow	(M)	The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.					
200 VA Transforme	r (CPT)	(K)	200 VA Control Power Transformer (for customer use).					
Speed pot		(Z)	Door mounted.					
Custom Nameplates	;	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.					

# Configured Drive NEMA Type 3R (Z1C3)

## **Model and Power Option Selection (Z1C3)**

			NEMA		L	egend:	A = Availa	ble N/A	= Not avail	able or no	t applical	ole	
Rated Input Voltage	Rated Output Current	Nominal HP *1	3R Configu red	Circuit Breaker (65 kAIC)	Circuit Breaker (100 kAIC)	Input Fuse	Two Motor "AND"	Two Motor "OR"	Load Reactor	Input Reactor	Noise Filter	Surge Suppressor	Space Heater
3	(Amps)		Z1C3	С	M	F	Α	Y	K	R	N	2	3
	2.4	0.5	D002										
	3.5	0.75	D003										
	4.6	1	D004										
	7.5	2	D007										
	10.6	3	D010										
	16.7	5	D016										
	24.2	7.5	D024										
	30.8	10	D030										
2021/	46.2	15	D046								N/A		
208 V 3-Phase	59.4	20	D059	Α	Α	Α	Α	Α	Α	Α		Α	Α
	74.8	25	D074										
	88	30	D088										
	114	40	D114										
	143	50	D143										
	169	60	D169										
	211	75	D211										
	273	100	D273										
	343	125	D343								Α		
	396	150	D396								^		

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

			NEMA		Le	gend: A	= Availal	ole N/A	= Not avail	able or not	applicat	ole	
Rated Input Voltage	Rated Output Current	Nominal HP *1	3R Config ured	Circuit Breaker (65 kAIC)	Circuit Breaker (100 kAIC)	Input Fuse	Two Motor "AND"	Two Motor "OR"	Load Reactor	Input Reactor	Noise Filter	Surge Suppressor	Space Heater
J	(Amps)		Z1C3	С	М	F	Α	Υ	K	R	N	2	3
	1.6	0.5 & 0.75	B001										
	2.1	1	B002										
	3.2	2	B003										
	4.8	3	B004										
	7.6	5	B007										
	11	7.5	B011										
	14	10	B014										
	21	15	B021										
	27	20	B027										
	34	25	B034										
	40	30	B040								N/A		
400.17	52	40	B52L										
480 V 3-Phase	52	40	B052	Α	Α	Α	Α	Α	Α	Α		Α	Α
	65	50	B065										
	77	60	B077										
	96	75	B096										
	124	100	B124										
	156	125	B156										
	180	150	B180										
	240	200	B240										
	302	250	B302										
	361	300	B361										
	414	350	B414								_		
	477	400	B477								Α		
	590	500	B590										

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

# Configured Drive NEMA Type 3R (Z1C3)

## **Dimensions and Data (Z1C3)**

### 208 V NEMA Type 3R

		Rated					E	Enclose	d, NEMA	3R
Rated Input Voltage	Z1C Configured Base No. Z1C3□□□□	Output Current	Nominal HP	Configured Box No.	Submittal Documents (Outline Drawing) (Schematic)	Drive Part No. CIMR-ZU	Overa	II Dimer (in)	sions	Weight (lb)
<b>J</b>		(Amps)			(33 3 333)		Н	W	D	(ID)
	D002	2.4	0.5			2A0011FAA				
	D003	3.5	0.75			2A0011FAA				
	D004	4.6	1	W1	DD.Z1.3R.W1.01	2A0011FAA	29.00	21.30	21.50	140
	D007	7.5	2	VV I	DS.Z1C3.01*1	2A0011FAA	29.00	21.30	21.50	140
	D010	10.6	3			2A0011FAA				
	D016	16.7	5			2A0017FAA				
	D024	24.2	7.5	W2	DD.Z1.3R.W2.01	2A0024FAA	35.00	23.90	21.50	200
	D030	30.8	10		DS.Z1C3.01*1	2A0031FAA	33.00	23.90	21.50	200
00011	D046	46.2	15		DD.Z1.3R.W3.01 DS.Z1C3.01 *1	2A0046FAA				
208 V 3-Phase	D059	59.4	20	W3		2A0059FAA	40.00	28.80	21.50	260
0 1 11.000	D074	74.8	25			2A0075FAA				
	D088	88	30	W4	DD.Z1.3R.W4.01	2A0088FAA	51.00	39.00	21.50	395
	D114	114	40	VV <del>-1</del>	DS.Z1C3.02*1	2A0114FAA	31.00	39.00	21.50	465
	D143	143	50			2A0143FAA				800
	D169	169	60			2A0169FAA				910
	D211	211	75	F1	DD.Z1.3R.F1.01	2A0211FAA	91.00	41.50	50.50	910
	D273	273	100		DS.Z1C3.02*1	2A0273FAA	91.00	41.50	30.50	1,150
	D343	343	125			2A0343AAA				1,200
	D396	396	150			2A0396AAA				1,250

<sup>\*1.</sup> Drives that have "OR" option refer to DS.Z1C3.09, DS.Z1C3.10, DS.Z1C3.11, DS.Z1C3.12; drives that have "AND" option refer to DS.Z1C3.05, DS.Z1C3.06, DS.Z1C3.07, DS.Z1C3.08

### 480 V NEMA Type 3R

	7400 5	Rated			0.1.111.15		E	Enclose	d, NEMA	3R
Rated Input Voltage	Z1C Configured Base No. Z1C3□□□□	Output Current	Nominal HP	Configured Box No.	Submittal Documents (Outline Drawing) (Schematic)	Drive Part No. CIMR-ZU	Overall Dimensions (in)			Weight (lb)
	2:00222	(Amps)			(Continuity)		Н	w	D	(ID)
	B001	1.1	0.5			4A0005FAA				
	B001	1.6	0.75			4A0005FAA				
	B002	2.1	1			4A0005FAA				
	B003	3.4	2	W1	DD.Z1.3R.W1.01 DS.Z1C3.01*1	4A0005FAA	29.00	21.30	21.50	140
	B004	4.8	3		50.2100.01	4A0005FAA				
	B007	7.6	5			4A0008FAA				
	B011	11	7.5	4A	4A0011FAA					
	B014	14	10			4A0014FAA				
	B021	21	15	DS.Z1C3.01	4A0021FAA	35.00	23.90	21.50	200	
	B027	27	20		4A0027FAA					
	B034	34	25			4A0034FAA				
	B040	40	30	W3	DD.Z1.3R.W3.01	4A0040FAA	40.00	28.80	21.50	260
	B52L	52	40	, ws	DS.Z1C3.01*1	4A0052FAB	40.00 20.0	20.60	21.50	200
480 V 3-Phase	B052	52	40			4A0052FAA				
3-Phase	B065	65	50			4A0065FAA	54.00			375
	B077	77	60	W4	DD.Z1.3R.W4.01	4A0077FAA		39.00	21.50	435
	B096	96	75	VV4	DS.Z1C3.02*1	4A0096FAA	51.00	39.00	21.50	465
	B124	124	100			4A0124FAA				505
	B156	156	125			4A0156FAA				795
	B180	180	150		DD.Z1.3R.F1.01	4A0180FAA	91.00	41.50	50.50	895
	B240	240	200		DS.Z1C3.02*1	4A0240FAA	91.00	41.50	50.50	895
	B302	302	250	F1		4A0302FAA				1,100
	B361	361	300		DD.Z1.3R.F1.03 DS.Z1C3.02*1	4A0361AAA	01.00	41.50	46.50	1,200
	B414	414	350	DD.Z1.3R.F1.03 DS.Z1C3.03*1		4A0414AAA	91.00	41.50	40.50	1,250
	B477	477	400	ГЭ	DD.Z1.3R.F2.01	4A0477AAA	01.00	66.50	42.50	1,700
	B590	590	500	F2	DS.Z1C3.04*1	4A0590AAA	91.00	66.50	43.50	1,900

The description of the descripti

# Redundant Drive Package NEMA Type 1 (Z1R1)

### Specifications: 480 V NEMA Type 1 (Z1R1)



The Z1000 Redundant Drive Package is engineered for use in critical HVAC building automation applications that require continuous reliable motor control.

The redundant drive package provides two Z1000 drives containing HVAC application-specific software macros and a real time clocks in a NEMA 1 (UL Type 1) enclosure to ensure uninterrupted operation in the event of drive fault.

The redundant drive package features a main input disconnect switch, semiconductor fuses for each drive, single input/output wiring points, a single control wiring point, two door-mounted keypads, a selectable Manual or Auto Transfer switch, an H/O/A switch, and an integral damper control circuit.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/ Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: 5 250 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Overtorque/undertorque detection

#### **Redundant Package Features**

- Standard Lockable Main Input Disconnect Switch
- · 115 Vac control transformer, fused
- Semiconductor Fuses for each VFD
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable Manual or Auto Transfer
- Drive A-Auto-Drive B switch
- · Hand-Off-Auto switch
- Single input/output wiring points
- · Single control wiring point
- Two door mounted keypads

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device.
- Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- Diagnostic fault indication
- · Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability

- Serial communication loss detection and selectable response strategy
- · Serial communication status
- 7 preset speeds
- · Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions
- · Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action
- Selectable energy savings mode

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3IEC 529
- IEEE C62.41
- UL, cUL listed
- BTL certified

### **Embedded Serial Communication Protocols**

- BACnet MSTP
- Modbus/Memobus
- · Siemens Apogee
- Johnson Controls Metasys

#### **Communication Options**

- FtherNet/IP
- LonWorks Interface


#### **Power Options**

 Optional Lockable Main Input Circuit Breaker with 100 kAIC panel rating

### **Model Number Configuration (Z1R1)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1R1)

### **Enclosure Options**

NEMA 1

(1) The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

# Redundant Drive Package NEMA Type 1 (Z1R1)

### **Power Options**

Circuit Breaker

The standard configuration provides a line input disconnect switch but no branch short circuit protection. Circuit breaker options are available. Option (M) is a 100 kAIC rated circuit breaker. When option (M) is specified, the drive package will be rated at 100 kAIC.

### **Control Options**

Ethernet/IP SI-EN3

(D) EtherNet/IP, option (D), requires the addition of an optional board.

\*1

(M)

LonWorks SI-W3 (L) LonWorks, option (L), requires the addition of an optional board.

\*1

Custom Nameplates (W) Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

### **Model Selection (Z1R1)**

Rated	Rated	Redundant Drive		Circuit Breaker	Dir	mensions (	in)	Ammunyimata	
Input	Output Current	Package Model No.	Nominal HP *2	(100 kAIC)	н	w	D	Approximate Weight (lb)	
Voltage	(Amps)	Z1R1B□□□		M	П	VV	D	ittoigiit (ii)	
	4.8	005	3					140	
	7.6	008	5					140	
	11	011	7.5					145	
	14	014	10		44.50			150	
	21	021	15		44.50			155	
	27	027	20			36.00	19.72	160	
	34	034	25			36.00	19.72	190	
	40	040	30					280	
480 V 3-Phase	52	052	40	Available	62.50			360	
0.1.1.000	65	065	50					450	
	77	077	60					450	
	96	096	75					470	
	124	124	100					760	
	156	156	125		84.16	41.26	26.39	910	
	180	180	150					950	
	240	240	200		85.70	69.76	23.70	TBD	
	302	302	250			Con	tact Yaska	wa	

<sup>\*2.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full Load Current, Three-Phase Alternating Current Motors at 480 volts.

<sup>\*1.</sup> Two (2) network control options, one option installed on each of the two drives within the redundant drive package.

## 12-Pulse Bypass Drive NEMA Type 1 (Z1B1J)

### Specifications: 480 V NEMA Type 1 (Z1B1J)



The 12-Pulse Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control and reduced harmonic distortion.

The bypass package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto keypad inside a NEMA 1 (UL Type 1) enclosure and a 3-contactor style bypass to allow motor operation from the drive or across the line.

The design also matches an isolation transformer with a tuned input reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: 7.5 to 250 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from
- Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed

3 Hz to 60 Hz

- PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Bypass Features**

- · Input, Output and Bypass Contactors
- Lockable Main Input Circuit Breaker with 100 kAIC panel rating
- Thermal motor overload relay, class 20
- 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- · Integral 12-Pulse Design
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Independent PI control for use with external dayion
- Differential PI feedback feature
- Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- Diagnostic fault indication
- · Cooling fan operating hours recorded

- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- Serial communication status
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- · LCD keypad: Hand-Off-Auto functions
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IFFF C62 41
- UL, cUL listed
- BTL certified

#### Options


- Soft Start Bypass
- EtherNet/IP
- LonWorks

# 12-Pulse Bypass Drive NEMA Type 1 (Z1B1J)

### **Model Number Configuration (Z1B1J)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



## **Options (Z1B1J)**

### **Enclosure Options**

NEMA 1

(1)

The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

### **Power Options**

Soft Start Bypass

(W)

Provides a solid-state adjustable soft starter for use when switching to bypass mode. Option (W) provides a solid-state soft-starter with adjustable ramp to reduce mechanical system stress typically associated with across-the-line bypass motor starts. Select option (W) if the application cannot tolerate the mechanical load stress caused by across-the-line bypass motor starts.

### **Control Options**

Ethernet/IP SI-EN3 (D) EtherNet/IP, option (D), requires the addition of an optional board.

LonWorks SI-W3 (L) LonWorks, option (L), requires the addition of an optional board.

Custom Nameplates (W)

Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

### **Model and Power Option Selection (Z1B1J)**

### **480 V Models and Power Options**

Datad Innut Valtage	Rated Output Current	Nominal HP <sup>*1</sup>	NEMA 1 12-Pulse Bypass	Soft Start Bypass
Rated Input Voltage	(Amps)	Nominal HP	Z1B1□□□□	W
	11	7.5	J011	
	14	10	J014	
	21	15	J021	
	27	20	J027	
	34	25	J034	
	40	30	J040	
	52	40	J052	
480 V 3-Phase	65	65 50 J0		Available
o i naco	77	60	J077	
	96	75	J096	
	124	100	J124	
	156	125	J156	
	180	150	J180	
	240	200	J240	
	302	250	J302	

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## 12-Pulse Bypass Drive NEMA Type 3R (Z1B3J)

### Specifications: 480 V NEMA Type 3R (Z1B3J)



The 12-Pulse Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control and reduced harmonic distortion.

The bypass package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto keypad inside a NEMA 3R (UL Type 3R) enclosure and lockable main input circuit breaker with a 3-contactor style bypass to allow motor operation from the drive or across the line.

The design also matches an isolation transformer with a tuned input reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 7.5 to 250 HP, 480 volt only.
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status Contactor
  - Control for External Bypass
  - Overtorque/undertorque detection

#### Bypass Features

- Input, Output and Bypass Contactors
- Lockable Main Input Circuit Breaker with 100 kAIC panel rating
- Thermal motor overload relay, class 20
- · 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 3R: -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Integral 12-Pulse Design
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- · Differential PI feedback feature
- Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- Diagnostic fault indication
- · Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy

- · Serial communication status
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL. cUL listed
- BTL certified


#### **Options**

- Soft Start Bypass
- Surge Suppressor
- Space Heater
- Custom Nameplate
- · Keypad Viewing Window
- EtherNet/IP
- LonWorks

### **Model Number Configuration (Z1B3J)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1B3J)

### **Enclosure Options**

NEMA 3R

(3) The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.

# 12-Pulse Bypass Drive NEMA Type 3R (Z1B3J)

### **Power Options**

Surge Suppressor	(2)	This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.
Space Heater	(3)	This option helps reduce condensation.
Soft Start Bypass	(W)	Provides a solid-state adjustable soft starter for use when switching to bypass mode. Option (W) provides a solid-state soft-starter with adjustable ramp to reduce mechanical system stress typically associated with across-the-line bypass motor starts. Select option (W) if the application cannot tolerate the mechanical load stress caused by across-the-line bypass motor starts.
<b>Control Options</b>		
Ethernet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.

### LonWorks SI-W3

(L) LonWorks, option (L), requires the addition of an optional board.

### Keypad Viewing Window

(M) The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.

### Custom Nameplates

(W)

Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## **Model and Power Option Selection (Z1B3J)**

### **480 V Models and Power Options**

Rated Input Voltage	Rated Output Current (Amps)	Nominal HP*1	NEMA 3R 12-Pulse Bypass Z1B3□□□□	Soft Start Bypass W	Surge Suppressor	Space Heater 3
14	10	J014				
21	15	J021				
27	20	J027				
34	25	J034				
40	30	J040				
52	40	J052				
65	50	J065				
77	60	J077				
96	75	J096				
124	100	J124				
156	125	J156				
180	150	J180				
240	200	J240				
302	250	J302				

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

# 12-Pulse Configured Drive NEMA Type 1 (Z1C1J)

### Specifications: 480 V NEMA Type 1 (Z1C1J)



The 12-Pulse Z1000 Configured drive is engineered to allow flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input circuit breaker and space for several power options inside a NEMA 1 (UL Type 1) enclosure.

The design also matches an isolation transformer with a tuned input reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 7.5 to 250 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Motor preheat function
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- Power loss ride through: 2 seconds
- Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection and selectable response strategy
- · Up/down floating point control capability
- Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
- 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5
  kHz
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Integral 12-Pulse Design
- Input circuit breaker (100 kAIC)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication

- · Diagnostic fault indication
- · Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- · LCD keypad: Hand-Off-Auto functions
- · Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed
- · BTL certified


### Options

- EtherNet/IP
- LonWorks

### **Model Number Configuration (Z1C1J)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1C1J)

### **Enclosure Options**

NEMA 1

(1) The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

### **Control Options**

EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

# 12-Pulse Configured Drive NEMA Type 1 (Z1C1J)

### **Model Selection (Z1C1J)**

Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *1	NEMA 1 12-Pulse Configured Available Models
			Z1C1□□□□
	11	7.5	J011
	14	10	J014
	21	15	J021
	27	20	J027
	34	25	J034
	40	30	J040
	52	40	J052
480 V 3-Phase	65	50	J065
0.1.1.000	77	60	J077
	96	75	J096
	124	100	J124
	156	125	J156
	180	150	J180
	240	200	J240
	302	250	J302

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## 12-Pulse Configured Drive NEMA Type 3R (Z1C3J)

### Specifications: 480 V NEMA Type 3R (Z1C3J)



The 12-Pulse Z1000 Configured NEMA 3R drive is engineered to allow flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input circuit breaker and space for several power options inside a NEMA 3R (UL Type 3R) enclosure.

The design also matches an isolation transformer with a tuned input reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: 7.5 to 250 HP. 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Motor preheat function
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- · Power loss ride through: 2 seconds
- · Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection and selectable response strategy
- · Up/down floating point control capability
- Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5 kHz
- Programmable security code
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 3R (IP14: -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- · Integral 12-Pulse Design
- Input circuit breaker (100 kAIC)
- Displacement power factor of 0.98 throughout the motor speed range
- · NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication
- · Diagnostic fault indication
- Cooling fan operating hours recorded

- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- · LCD keypad: Hand-Off-Auto functions
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- · UL, cUL listed
- BTL certified


- Surge Suppressor
- Space Heater
- Custom Nameplate
- Keypad Viewing Window
- · EtherNet/IP
- LonWorks

# 12-Pulse Configured Drive NEMA Type 3R (Z1C3J)

### **Model Number Configuration (Z1C3J)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1C3J)

### **Enclosure Options**

NEMA 3R	(3)	The drive and configured options are provided in a NEMA Type 3R ventilated
		enclosure, large enough to accommodate any or all of the Configured package
		options.

### **Power Options**

•		
Surge Suppressor	(2)	This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.
Space Heater	(3)	This option helps reduce condensation.
<b>Control Options</b>		

LonWorks	
SI-W3	

EtherNet/IP

SI-EN3

(D)

(L) LonWorks, option (L), requires the addition of an optional board.

EtherNet/IP, option (D), requires the addition of an optional board.

Keypad Viewing (M) The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.

Custom Nameplates Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

### **Model and Power Option Selection (Z1C3J)**

(W)

Rated Input Voltage	Rated Output Current	Nominal HP*1	NEMA 3R 12-Pulse Configured	Surge Suppressor	Space Heater
	(Amps)		Z1C3□□□□	2	3
	11	7.5	J011		
	14	10	J014		
	21	15	J021		
	27	20	J027		
	34	25	J034		
	40	30	J040		
400.14	52	40	J052		
480 V 3-Phase	65	50	J065	Available	Available
	77	60	J077		
	96	75	J096		
	124	100	J124		
	156	125	J156		
	180	150	J180		
	240	200	J240		
	302	250	J302		

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## 18-Pulse Bypass Drive NEMA Type 1 (Z1B1K)

### Specifications: 480 V NEMA Type 1 (Z1B1K)



The 18-Pulse Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control and reduced harmonic distortion.

The bypass package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto keypad inside a NEMA 1 (UL Type 1) enclosure and a 3-contactor style bypass to allow motor operation from the drive or across

The design also matches an autotransformer with a tuned balance reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: Ratings: 5 to 250 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150%) Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 VDC (20 K Ohm)
  - 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status Contactor
  - Control for External Bypass
  - Overtorque/undertorque detection

#### **Bypass Features**

- · Input, Output and Bypass Contactors
- Lockable Main Input Circuit Breaker with 100 kAIC panel rating
- Thermal motor overload relay, class 20
- 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C  $\,$  Built-in BACnet protocol (BTL certified) (-4 °F to 158 °F)
- Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Integral 18-Pulse Design
- Displacement power factor of 0.98 throughout Flash upgradeable firmware the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- · Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- · Independent PI control for use with external
- · Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication
- · Diagnostic fault indication
- · Cooling fan operating hours recorded

- · VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- Serial communication status
- 7 preset speeds
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- · LCD keypad: Hand-Off-Auto functions
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive

#### Standards


- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62 41
- · UL, cUL listed
- · BTL certified

- · Soft Start Bypass
- EtherNet/IP
- LonWorks

### **Model Number Configuration (Z1B1K)**

**Step 1.** Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1B1K)

### **Enclosure Options**

NEMA Type 1

(1) The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

### **Power Options**

Soft Start Bypass

Provides a solid-state adjustable soft starter for use when switching to bypass mode. Option (W) provides a solid-state soft-starter with adjustable ramp to reduce mechanical system stress typically associated with across-the-line bypass motor starts. Select option (W) if the application cannot tolerate the mechanical load stress caused by across-the-line bypass motor starts.

### **Control Options**

Ethernet/IP

(D) EtherNet/IP, option (D), requires the addition of an optional board.

SI-EN3

LonWorks

(L) LonWorks, option (L), requires the addition of an optional board.

SI-W3

(W)

# 18-Pulse Bypass Drive NEMA Type 1 (Z1B1K)

Custom Nameplates (W)

Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

### **Model and Power Option Selection (Z1B1K)**

Dated Innet Valtage	Rated Output Current	No maior al LID *1	NEMA 1 18-Pulse Bypass	Soft Start Bypass	
Rated Input Voltage	(Amps)	Nominal HP*1	Z1B1□□□□	W	
	7.6	5	K007		
	11	7.5	K011		
	14	10	K014		
	21	15	K021		
	27	20	K027		
	34 40 52 65 77	25	K034		
		30	K040	l	
480 V		40	K052	Available	
3-Phase		50	K065	Available	
		60	K077		
	96	75	K096		
	124	100	K124		
	156	125	K156		
	180	150	K180		
	240	200	K240		
	302	250	K302		

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## 18-Pulse Bypass Drive NEMA Type 3R (Z1B3K)

### Specifications: 480 V NEMA Type 3R (Z1B3K)



The 18-Pulse Z1000 Bypass is engineered for use in HVAC building automation applications that require reliable motor control and reduced harmonic distortion.

The bypass package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto keypad inside a NEMA 3R (UL Type 3R) enclosure and lockable main input circuit breaker with a 3-contact style bypass to allow motor operation from the drive or across the line.

The design also matches an autotransformer with a tuned balance reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 5 to 250 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 4 programmable multi-function output relays (Form C rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status Contactor
  - Control for External Bypass
  - Overtorque/undertorque detection

#### **Sypass Features**

- Input, Output and Bypass Contactors
- Lockable Main Input Circuit Breaker with 100 kAIC panel rating
- Thermal motor overload relay, class 20
- · 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback with two adjustable wait time functions
- Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 3R (IP14): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Integral 18-Pulse Design
- Displacement power factor of 0.98 throughout the motor speed range
- · NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- · Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- · Input and output terminal status indication
- Diagnostic fault indication
- · Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy

- · Serial communication status
- 7 preset speeds
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed
- BTL certified


- Soft Start Bypass
- Surge Suppressor
- Space Heater
- · Custom Nameplate
- · Keypad Viewing Window
- EtherNet/IP
- LonWorks

## 18-Pulse Bypass Drive NEMA Type 3R (Z1B3K)

### **Model Number Configuration (Z1B3K)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1B3K)

### **Enclosure Options**

NEMA 3R

(3) The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.

## **Power Options**

Surge Suppressor	(2)	This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.
Space Heater	(3)	This option helps reduce condensation.
Soft Start Bypass	(W)	Provides a solid-state adjustable soft starter for use when switching to bypass mode. Option (W) provides a solid-state soft-starter with adjustable ramp to reduce mechanical system stress typically associated with across-the-line bypass motor starts. Select option (W) if the application cannot tolerate the mechanical load stress caused by across-the-line bypass motor starts.
Control Options	;	
Ethernet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Keypad Viewing Window	(M)	The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

# 18-Pulse Bypass Drive NEMA Type 3R (Z1B3K)

### **Model and Power Option Selection (Z1B3K)**

Rated Input	Rated Output Current (Amps)	Nominal HP*1	NEMA 3R 18-Pulse Bypass	Soft Start Bypass	Surge Suppressor	Space Heater
Voltage	Current (Amps)		Z1B3□□□□	W	2	3
	7.6	5	K007			
	11	7.5	K011			
	14	10	K014			
	21	15	K021			
	27	20	K027			
	34	25	K034			
	40	30	K040			
480 V	52	40	K052	Available	Available	Available
3-Phase	65	50	K065	Available	Available	Available
	77	60	K077			
	96	75	K096			
	124	100	K124			
	156	125	K156			
	180	150	K180			
	240	200	K240			
	302	250	K302			

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## 18-Pulse Configured Drive NEMA Type 1 (Z1C1K)

### Specifications: 480 V NEMA Type 1 (Z1C1K)



The 18-Pulse Z1000 Configured NEMA 1 drive is engineered to allow flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input circuit breaker and space for several power options inside a NEMA 1 (UL Type 1) enclosure.

The design also matches an autotransformer with a tuned balance reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### Performance Features

- VT Ratings: 5 to 250 HP, 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Motor preheat function
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- · Power loss ride through: 2 seconds
- Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection and selectable response strategy
- · Up/down floating point control capability
- Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5 kHz
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Integral 18-Pulse Design
- Input circuit breaker (100 kAIC)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication

- · Diagnostic fault indication
- · Cooling fan operating hours recorded
- VFD efficiency: 98% at full-speed; 96% at halfspeed
- "S-curve" soft start / soft stop capability
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions with a built-in copy feature
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### Standards

- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed
- BTL certified


- EtherNet/IP
- LonWorks

# 18-Pulse Configured Drive NEMA Type 1 (Z1C1K)

### **Model Number Configuration (Z1C1K)**

**Step 1.** Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1C1K)

### **Control Options**

EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

## **Model and Power Option Selection (Z1C1K)**

Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *1	NEMA 1 18-Pulse Configured
	,		Z1C1□□□□
	7.6	5	K007
	11	7.5	K011
	14	10	K014
	21	15	K021
	27	20	K027
	34	25	K034
	40	30	K040
480 V	52	40	K052
3-Phase	65	50	K065
	77	60	K077
	96	75	K096
	124	100	K124
	156	125	K156
	180	150	K180
	240	200	K240
	302	250	K302

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## 18-Pulse Configured Drive NEMA Type 3R (Z1C3K)

### Specifications: 480 V NEMA Type 3R (Z1C3K)



The 18-Pulse Z1000 Configured NEMA 3R drive is engineered to allow flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000 drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input circuit breaker and space for several power options inside a NEMA 3R (UL Type 3R enclosure. The design also matches an autotransformer with a tuned balance reactor to provide a phase shift that reduces harmonic distortion for cleaner power.

Popular building automation communication protocols BACnet, Siemens APOGEE, Johnson Controls Metasys, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings: 5 to 250 HP. 480 Vac
- Overload capacity: 110% for 60 seconds (150% Peak)
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Motor preheat function
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Controlled speed range 40:1
- · Power loss ride through: 2 seconds
- Torque limiting: 30 to 180%
- Auto restart after power loss or resettable fault, selectable, programmable
- Serial communications loss detection and selectable response strategy
- Up/down floating point control capability
- Stationary motor auto-tuning
- 140% starting torque capability, available from 3 Hz to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc (20 K Ohm) 4 to 20 mA DC (250 Ohm)
- Adjustable carrier frequency, from 1 kHz to 12.5 kHz
- Programmable security code
- 7 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 3 programmable multi-function output relays (Form A rated 2 amps @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±5%
- Ambient service temperature: NEMA 3R (IP14): -10 °C to 40 °C (14 °F to 104 °F)
- Ambient storage temperature: -20 °C to 70 °C (-4 °F to 158 °F)
- · Humidity: 0% to 95% non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### **Design Features**

- Integral 18-Pulse Design
- Input circuit breaker (100 kAIC)
- Displacement power factor of 0.98 throughout the motor speed range
- NEC rated input / output amps
- Internal EMI/RFI filter complies with IEC 61800-3 restricted distribution for first environment (Category 2)
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Drive internal PI closed loop control with selectable engineering units
- Independent PI control for use with external device
- · Differential PI feedback feature
- · Direct or reverse acting speed signal
- Sleep function in both closed loop and open loop control
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- 24 Vdc, 150 ma transmitter power supply
- Input and output terminal status indication
- · Diagnostic fault indication
- Cooling fan operating hours recorded

- VFD efficiency: 98% at full-speed; 96% at halfspeed
- · "S-curve" soft start / soft stop capability
- Built-in BACnet protocol (BTL certified)
- Modbus/Memobus accessible via RS-422/485 communication, which is standard
- "Kinetic Energy Braking" (KEB) function stops the motor in up to half the time it would take without this function
- LCD keypad: Hand-Off-Auto functions with a built-in copy feature
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive action

#### **Standards**


- UL 508A (Industrial Control Panels)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- IEC 61800-5-1 (LVD)
- EN 61800-3
- IEC 529
- IEEE C62.41
- UL, cUL listed
- · BTL certified

- Surge Suppressor
- · Space Heater
- Custom Nameplate
- · Keypad Viewing Window
- EtherNet/IP
- LonWorks

### **Model Number Configuration (Z1C3K)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### Options (Z1C3K)

### **Enclosure Options**

NEMA 3R (3) The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.

### **Power Options**

Surge Suppressor (2) This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.

## Space Heater (3) This option helps reduce condensation.

### **Control Options**

EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.

# 18-Pulse Configured Drive NEMA Type 3R (Z1C3K)

Keypad Viewing (M) The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.

Custom (W) Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

### **Model and Power Option Selection (Z1C3K)**

Rated Input Voltage	Rated Output Current	Nominal HP*1	NEMA 3R 18-Pulse Configured	Surge Suppressor	Space Heater
	(Amps)		Z1C3□□□□	2	3
	7.6	5	K007		
	11	7.5	K011		
	14	10	K014		
	21	15	K021		
	27	20	K027		Available
	34	25	K034		
	40	30	K040		
480 V	52	40	K052	Available	
3-Phase	65	50	K065		
	77	60	K077		
	96	75	K096		
	124	100	K124		
	156	125	K156		
	180	150	K180		
	240	200	K240	K240	
	302	250	K302		

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

Note: Consult factory for outline drawings and schematics.

## Z1000U HVAC MATRIX Drive

### **Z1000U Specifications: 200 to 240 V and 380 to 480 V**



The Z1000U HVAC MATRIX drive combines superior harmonic mitigation, input power factor control, and energy saving capabilities in a design specifically suited for use in building automation applications requiring reliable motor control.

The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications, and features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy.

Popular building automation communication protocols, BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings:
  - 200 to 240 V. 10 to 100 HP 380 to 480 V, 7.5 to 350 HP
- V/f Control, Open Loop Vector Control for PM
- Overload capacity: 120% for 60 seconds
- 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- Auto restart after power loss or resettable fault, selectable, programmable
- Up/down floating point control capability
- Stationary motor auto-tuning
- 150% starting torque, available from 3 to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms)
  - 4 to 20 mA/0 to 20 mAdc (250 Ohms)
- Adjustable carrier frequency, from 4 kHz to 10
- Programmable security code
- 8 programmable multi-function input terminals . (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection

#### **Service Conditions**

- Input voltage: 200 to 240 Vac, 380 to 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Ambient service temperature: Open Type (IP00): -10 °C to 50 °C (14 °F to 122 °F)
- Enclosure rating: Protected IPOO/Open-Chassis

- Ambient storage temperature: -20 °C to 60 °C Energy Savings Monitor (-4 °F to 140 °F)
- Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating
- Service factor: 1.0
- 10 to 20 Hz: 9.8 m/s<sup>2</sup> 20 to 55 Hz: 5.9 m/s<sup>2</sup>  $(2\square 0028 \text{ to } 2\square 0081 \text{ and } 4\square 0011 \text{ to } 4\square 0077),$ 2.0 m/s $^2$  (2 $\square$ 0104 to 2 $\square$ 0248 and 4 $\square$ 0096 to
- Plenum mounting capable (IP20)

#### **Design Features**

- Standard LCD Multi-lingual keypad, Full-text. Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- Differential PID feedback feature
- Sleep function in both closed loop and open
- Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- Input and output terminal status indication
- Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at full-
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- Eco-Mode to achieve near across-the-line THD and quietest operation

- Motor preheat function
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function
- Fan failure detection and selectable drive
- Built-in EMC Filter
- Built-in line fuses, 100 kAIC
- Energy Savings Low Power Loss Design
- Compact Package
- Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS
- Optimal Speed Command Search

#### Standards

- UL 508C (Power Conversion)
- CSA 22.2 No. 14-95 (Industrial Control Equipment)
- UL 1995 (Plenum)
- CE mark 2006/95/EC LVD
- CE mark 2004/108/EC
- · ROHS Compliant
- IEC 61800-5-1 (LVD)
- EN 61800-3:2004
- IFC 529
- IEEE C62.41
- · UL, cUL listed; CE marked
- · BACnet (BTL) Certified

- · LonWorks Interface
- FtherNet/IP
- · Modbus TCP/IP

# Z1000U HVAC MATRIX Drive

### Z1000U Model Selection 200 to 240 V

	Ra	ting	Standard Enclosure	
Rated Input Voltage	Rated Output Amps *1 *2	HP *3 240 V (208 V)	Model Number CIMR-ZU2E□□□□AUA With built-in EMC noise filter.	
	28	10 (7.5)	0028	
	42	15 (10)	0042	
	54	20 (15)	0054	
	68	25 (20)	0068	
200 to 240 V	81	30 (25)	0081	
3-Phase	104	40 (30)	0104	
	130	50 (40)	0130	
	154	60 (50)	0154	
	192	75 (60)	0192	
	248	100 (75)	0248	

<sup>\*1.</sup> The rated output current of the drive should be equal to or greater than the motor rated current.

#### Z1000U Model Selection 380 to 480 V

	Ra	ting	Standard Enclosure	
Rated Input Voltage	Rated Output Amps *1 *2	Nominal HP*3	Model Number CIMR-ZU4E□□□□AUA With built-in EMC noise filter.	
	11	7.5	0011	
	14	10	0014	
	21	15	0021	
	27	20	0027	
	34	25	0034	
	40	30	0040	
	52	40	0052	
	65	50	0065	
380 to 480 V	77	60	0077	
3-Phase	96	75	0096	
	124	100	0124	
	156	125	0156	
	180	150	0180	
	216	175	0216	
	240	200	0240	
	302	250	0302	
	361	300	0361	
	414	350	0414	

<sup>\*1.</sup> The rated output current of the drive should be equal to or greater than the motor rated current.

<sup>\*2.</sup> Carrier frequency is set to 4 kHz. Current derating is required to raise the carrier frequency.

<sup>\*3.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at (208) or 240 volts.

<sup>\*2.</sup> Carrier frequency is set to 4 kHz. Current derating is required to raise the carrier frequency.

<sup>\*3.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

### **Z1000U Options**

### **End Cap Kits NEMA 1**

This option consists of a top and bottom cover to convert a protected IPOO/Open Type drive to a IP2O/NEMA 1, UL Type 1 enclosed unit. This option DOES NOT provide additional space for mounting auxiliary components (i.e., circuit breaker, input fuses, reactor, etc.).

Rated Input Voltage	Drive Model Number CIMR-ZU2E□□□□AUA	Part Number
	0028	EZZ022745A
	0042	
	0054	EZZ022745B
	0068	EZZ022143B
200 to 240 V	0081	
3-Phase	0104	EZZ022745C
	0130	LZZ022143C
	0154	EZZ022745D
	0192	EZZ022143D
	0248	EZZ022745E
Rated Input Voltage	Drive Model Number CIMR-ZU4E□□□□AUA	Part Number
	0011	
	0014	
	0021	EZZ022745A
	0027	
	0034	
	0040	
	0052	EZZ022745B
	0065	LL2022140B
380 to 480 V	0077	
3-Phase	0096	EZZ022745C
	0124	L220221430
	0156	EZZ022745D
	0180	
	0216	EZZ022745E
	0240	
	0302	
	0361	EZZ022745F
	0414	

### 24 Vdc Control Power

Model No.	Option Name	Description
PS-U10L	24 V Control Power (200 V Drives)	The 24 V Power Supply option supplies the drive control circuit with power when there is no main circuit power. The option provides external power to the control circuit only. It will
PS-U10H	24 V Control Power (400 V Drives)	not provide power to the drive main circuit. The option lets users access network communications, digital operator navigation, I/O data, and read fault and parameter data

# Z1000U HVAC MATRIX Drive

### **External Heatsink Kits NEMA 1**

**External Heatsink Kit**: Allows drives to be mounted with the drive's heatsink external (NEMA 1 backside) to the enclosure. Option kit for customer mounting. Larger standard drives include brackets.

Rated Input Voltage	Drive Model Number CIMR-ZU2E□□□□□AUA	Part Number
	0028	UUX001072
	0042	
	0054	UUX001073
	0068	000001073
200 to 240 V	0081	
3-Phase	0104	UUX001074
	0130	000001074
	0154	UUX001075
	0192	000001075
	0248	*1
Rated Input Voltage	Drive Model Number CIMR-ZU4E□□□□AUA	Part Number
	0011	
	0014	
	0021	UUX001072
	0027	
	0034	
	0040	
	0052	UUX001073
	0065	30/10/10
380 to 480 V	0077	
3-Phase	0096	UUX001074
	0124	00/100 101 1
	0156	UUX001075
	0180	30,001010
	0216	
	0240	
	0302	*1
	0361	
	0414	

<sup>\*1</sup> Required brackets are included with the drive.

### **Z1000U Control and Communication Options**

These cards, cables, and devices add control functionality to the standard drive. Items are shipped loose, unmounted.

### **Digital Operator and Software**

Model No.	Option Name	Description			
UOP000016	Distitut On acates (LCD)	This option is the standard digital operator found on the drive. This option is only required if the original digital operator is lost or damaged. If used as a remote operator, the standard digital operator may be used, but then requires Installation Set A (EZZ020642A) for panel or door mounting and Remote Operator Cable (UWR0051 or UWR0052), each sold separately. Features include:			
(JVOP-183)	Digital Operator (LCD)	LCD keypad display, 5 lines x 16 characters, backlit			
		• 7 languages			
		Copy function			
		Mounts to RJ-45 keypad port			
EZZ020642A	LCD/LED Keypad Installation Set A (Remote Operator Mounting Bracket Kit)	This is a bracket to which the LCD Digital Remote Operator (JVOP-183) attaches, and has (4) threaded holes and screws to attach to the cover of an enclosure. The kit contains (2) screws to mount the Operator to the bracket and (4) screws to attach the bracket to the enclosure.			
EZZ020642B	LCD/LED Keypad Installation Set B (Remote Operator Mounting Bracket Kit)	Contains a similar bracket that the keypad attaches to and has non-threaded holes for mounting to an enclosure that has the screws attached to the enclosure already. The kit contains (2) screws to mount the keypad to the bracket and (4) nuts to attach the bracket to the customer supplied screws attached to the enclosure.			
UUX000922	Keypad Adapter Kit	This kit can be used when a "new" Z1000 keypad is replacing an "old style" key pad used with E7-based Z1000 drives. This kit will allow enclosure door mounted key pad to be upgraded from E7 style to the Z1000 style digital key pad.			
UWR0051	Operator Cable, Remote (1 meter)	These cables are used to connect the Remote Digital Operator (JVOP-18□). They are available in			
UWR0052	Operator Cable, Remote (3 meter)	one (1) or three (3) meter lengths.			
UUX000526 (Blank Membrane)		This option is used to extend an LCD or LED Digital Remote Operator to the wall of a separatel specified, oversized UL Type 3R, 4, 4X, or 12 enclosure (IPX6 environment). Item includes a			
UUX000527 (Yaskawa Logo Membrane)	Operator Kits, NEMA Type 3R/4X	faceplate bezel with digital operator brackets and membrane to cover the operator cutout in the enclosure door, a 3-foot cable, a 10-foot cable, and a 1:1 template for cutting the necessary cuin the enclosure. Keypad can be removed after kit installation. Designed for use with 1000 selection Digital Remote Operators (sold separately). Connects to RJ-45 port and mounts to enclosure			
UNP00233-3 (Yaskawa Logo)	Overlay, Keypad, Self-adhesive	This membrane is used to cover the operator cutout in the enclosure door to which the keypad has			
UNP00233-5 (Blank)	Overlay, Reypau, Sell-auriesive	been remotely mounted.			
UOP000017 (Yaskawa Logo Faceplate Membrane)	UL Rated Remote Outdoor Operator/	UL Rated Remote Outdoor Operator / Mounting Kit. This option provides all you will need to remotely mount the drive's Digital Operator to the door/wall of a separately specified, oversized UL Type 1, 3R, 4, 4X, or 12 enclosure (IPX6 environment). This kit includes: One JVOP-183R Digital Operator providing RTC, HOA, and outdoor rated LCD display, a faceplate bezel with digital operator brackets			
UOP000019 (Blank Faceplate Membrane)	Mounting Kit	and membrane to cover the operator cutout in the enclosure door, a 3-foot cable, and a 1:1 template for cutting the necessary cutouts in the enclosure. Mounting hardware is included. Keypad can be removed after kit installation. Connects to RJ-45 port and mounts to enclosure wall.			
SW.DW.40	DriveWizard® HVAC Software	This optional software package allows upload and download of parameters via PC for data storage and for programming multiple drives. The software also includes graphing and monitoring tools. It is a Windows-based program designed to make startup, commissioning, and troubleshooting the drive as simple as possible. Refer to our website at <b>www.yaskawa.com</b> to download the software, and for more information, including minimum system requirements and cable information to interface a PC to the drive.			
UWR-00638	USB Interface Cable	This 10-foot male USB-A to male USB-B cable provides a USB-to-USB connection from PC to the drive.			
UWR-01076-1	Flash Write Cable	This 6-foot cable connects a PC's 9-pin serial port to the drive's keypad port for updating the drive's firmware, flashing with custom firmware, or updating a network communication option board. It is used with the Flash Tool feature of the DriveWizard® HVAC software.			
UWR00468-2	PC Interface Cable	This 6-foot cable interconnects the drive keypad port to the 9-pin communication port on a PC. This cable is used in conjunction with DriveWizard® HVAC software.			

### **Support Tools**

Model No.	Option Name	Description
JVOP-181	USB Copy Unit (Y-Stick)	This option allows the drive to connect to the USB port on a PC. It can read, copy and verify drive parameter settings from one drive to another like drive. The unit plugs into the RJ-45 port on the front of the digital operator. Refer to our website at www.yaskawa.com to download the software.
	CopyUnitManager Software for USB Copy Unit (Y-Stick)	This option allows the user to transfer and save parameter files from the Copy Unit (JVOP-181), sold separately, to a PC and vice versa. Refer to our website at www.yaskawa.com to download the software.

# Z1000U HVAC MATRIX Drive

#### **Network Communications**

Model No.	Option Name	Description
SI-W3	LonWorks	This option is compatible with the LonMark Interoperability Association and complies with the Functional Profile for a Variable Frequency Motor Drive. Network connectivity is facilitated by either a Phoenix-style screw termination or RJ-45 connector. Mounts at option connector CN5-A.
SI-EN3	EtherNet/IP	This option complies with the EtherNet/IP protocol specification, and allows for communication over 10/100 Mbps Ethernet networks. This option has the ability to configure the IP Address from a user specified IP address, from a DHCP host, or from a BootP host. The IP address can be set from the drive keypad or from the network. All parameters, diagnostics, and operational commands are accessible via EtherNet/IP. The web interface allows management of diagnostic information through a standard web browser. The embedded web pages include the main page, drive status page, network monitor page, and documentation page. Mounts at option connector CN5-A.
SI-EM3	Modbus TCP/IP	This option complies with the Modbus TCP/IP protocol specification. This allows for Modbus communication over 10/100 Mbps Ethernet networks. This option has the ability to configure the IP Address from a user-specified IP address, from a DHCP host, or from a BootP host. All parameters, diagnostics, and operational commands are accessible via Modbus TCP/IP. This option supports up to 10 simultaneous PLC/PC connections.  Mounts at option connector CN5-A.
SI-EN3D	EtherNet/IP with device level ring (DLR)	This option complies with the EtherNet/IP protocol specification. This allows for communication over 10/100 Mbps Ethernet networks. The dual port hardware provides the user the choice of wiring in a star, line or ring configuration. For a ring configuration, device level ring (DLR) is available on this option card. This option has the ability to configure the IP Address from a user specified IP address, from a DHCP host, or from a BootP host. All parameters, diagnostics and operational commands are accessible via EtherNet/IP. Auto-tuning the motor is also possible through this option using the DriveWizard PC program.  Mounts at option connector CN5-A.
SI-EM3D	Modbus TCP/IP – Dual Port	This option complies with the Modbus TCP/IP protocol specification. This allows for Modbus communication over 10/100 Mbps Ethernet networks. The dual port hardware provides the user the choice of wiring in a star, line or ring configuration. For a ring configuration, rapid spanning tree protocol (RSTP) is available on this option card. This option has the ability to configure the IP Address from a user specified IP address, from a DHCP host, or from a BootP host. All parameters, diagnostics and operational commands are accessible via Modbus TCP/IP. Auto-tuning the motor is also possible through this option using the DriveWizard PC program. This option supports up to 10 simultaneous PLC/PC connections.  Mounts at option connector CN5-A.

## **Z1000U Dimensions and Data**

### 200 to 240 V

Units: mm (in)

Rated Input	Model Number	Units: mm (in)					Heat Loss (Watts)		
Voltage	CIMR- ZU2E□□□□AUA	Н	w	D	Wt. kg (lb)	Drawing Number	Heatsink	Internal	Total
	0028	480 (18.89)	250 (9.84)	360 (14.17)	21 (46)	DD.Z1KU.FR1.IP00	659	103	762
	0042		264		33		854	168	1022
	0054	650		264 (10.39) 420 (16.53)	(73)	DD.Z1KU.FR2.IP00	1037	195	1232
	0068	(25.60)	(10.39)		36 (79)		1295	225	1520
200 to 240 V	0081	]					1420	238	1658
3-Phase	0104	816	264	450 (17.71)		DD.Z1KU.FR3.IP00	1696	282	1978
	0130	(32.12)	(10.39)				2157	341	2498
	0154	900	415	403	115	115	2441	366	2807
	0192	(38.97)	(16.33)	(15.86)	(254)	DD.Z1KU.FR4.IP00	3064	447	3511
	0248	1132 (44.56)	490 (19.29)	450 (17.71)	181 (399)	DD.Z1KU.FR4.5.IP00	3785	578	4363

### 380 to 480 V

Units: mm (in)

Rated Input	Model Number	Ur	its: mm (i	in)			Heat Loss (Watts)		
Voltage	CIMR- ZU4E□□□□AUA	Н	w	D	Wt. kg (lb)	Drawing Number	Heatsink	Internal	Total
	0011						452	80	532
	0014						459	79	538
	0021	480 (18.89)	250 (9.84)	360 (14.17)	21 (46)	DD.Z1KU.FR1.IP00	641	105	746
	0027	(10.00)	(0.01)	(11117)	(10)		675	106	781
	0034						798	124	922
	0040	650	264		33	DD.Z1KU.FR2.IP00	877	174	1051
	0052			264 (10.39) 420 (16.53)	(73)		1109	209	1318
	0065	(25.60)	(10.39)		36 (79)		1369	240	1609
380 to 480 V	0077	1					1479	251	1730
3-Phase	0096	816		450 (17.71)	63 (139)	DD.Z1KU.FR3.IP00	1715	290	2005
	0124	(32.12)				DD.21KU.FR3.1F00	2256	362	2618
	0156	990	990 415 (38.97) (16.33)	403 (15.86)	115 (254)	DD.Z1KU.FR4.IP00	2857	421	3278
	0180	(38.97)					3316	482	3798
	0216	1132	490	450	181	DD.Z1KU.FR4.5.IP00	3720	587	4307
	0240	(44.56)	(19.29)	(17.71)	(399)	טט.ב ואט.רא4.ס.וויטט	3897	600	4497
	0302						5202	857	6059
	0361	1132 (44.56)	695 (27.36)	450 (17.71)	267 (589)	DD.Z1KU.FR5.IP00	5434	863	6297
	0414		(2.1.00)		(559)		6444	1012	7456

## Z1000U MATRIX Bypass Drive NEMA Type 1 (Z1D1)

### Specifications: 208 and 480 V NEMA Type 1 (Z1D1)



The Z1000U MATRIX Bypass combines excellent harmonic mitigation, input power factor control, and energy saving capabilities in a design specifically suited for use in HVAC building automation applications that require reliable motor control.

The bypass package provides a Z1000U MATRIX drive in a NEMA 1 (UL Type 1) enclosure with input circuit breaker, and 2-contactor style bypass to allow motor operation from the drive or across the line. The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications.

The Z1000U features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy. Popular building automation communication protocols BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings:
  - 208 V, 7.5 to 75 HP 480 V, 7.5 to 350 HP
- V/f Control, Open Loop Vector Control for PM
- Overload capacity: 120% for 60 seconds
- · 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- · Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- · Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- · Stationary motor auto-tuning
- 150% starting torque capability, available from 3 to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms) - 4 to 20 mA/0 to 20 mAdc (250 Ohms)
- **Bypass Features**
- Output and bypass contactors
- · Lockable main input circuit breaker
- Thermal motor overload relay, class 20
- 115 Vac control transformer, fused
- · Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback and two adjustable wait time functions
- · Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes.

#### **Design Features**

- NEC rated input / output amps
- Standard LCD Multi-lingual keypad, Full-text, Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls

- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- · Differential PID feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- Input and output terminal status indication
- · Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at full-speed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status
- Adjustable carrier frequency, 4 kHz to 10 kHz
- Programmable security code
- 8 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- Energy Savings Monitor
- Eco-Mode to achieve near across-the-line THD and quietest operation

- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- · "Bumpless" transfer between Hand and Auto
- Emergency override can be used as "smoke purge"
- Fan failure detection and selectable drive action
- · Built-in EMC Filter
- Built-in input fuses
- Input circuit breaker (100 kAIC)
- Energy Savings Low Power Loss Design
- · Compact Package
- Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS
- Optimal Speed Command Search

#### **Service Conditions**

- Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Ambient service temperature: NEMA 1 (IP20): -10 °C to 40 °C (14 °F to 104 °F)
- Maximum ambient storage temperature: -20 to 60 °C (-4 to 140 °F)
- Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### Standards


• UL 508A (Industrial Control Panels)

- 3-Contactor Bypass
- Drive Service Switch
- 5% Output Reactor
- Soft-start Bypass
- Custom Nameplate
- Speed Pot (door mounted)
- 200 VA Control Power Transformer
- LonWorks InterfaceEtherNet/IP

### **Model Number Configuration (Z1D1)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



<sup>\*</sup> An EMC filter is internal to the Z1000U drive.

### Options (Z1D1)

### **Enclosure Options**

NEMA 1

(1) The drive and Configured options are provided in a NEMA Type 1 ventilated enclosure, large enough to accommodate any or all of the Configured package options.

# Z1000U MATRIX Bypass Drive NEMA Type 1 (Z1D1)

### **Power Options**

Drive Input Circuit	(B, G)	For a 3-contactor bypass that removes power from the drive, select option (B). Drive service switch that removes power from the drive, select option (G).
Output Reactor	(K)	No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long lead-lengths or noise reduction).
Soft Start Bypass	(W)*1	Provides a solid-state adjustable soft starter for use when switching to bypass mode. Option (W) provides a solid-state soft-starter with adjustable ramp to reduce mechanical system stress typically associated with across-the-line bypass motor starts. Select option (W) if the application cannot tolerate the mechanical load stress caused by across-the-line bypass motor starts.  Note *1: The following Z1D1 models have a short circuit withstand rating of 65 kA RMS symmetrical when option W is specified:  - Z1D1B011 to Z1D1B156  - Z1D1D024 to Z1D1D143  Other Z1D1 models have a short circuit withstand rating of 100 kA RMS symmetrical when option W is specified.

### **Control Options**

Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.
EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Speed pot	(Z)	Door mounted.
200 VA Transformer (CPT)	(K)	200 VA Control Power Transformer (for customer use).

### **Model and Power Option Selection (Z1D1)**

### **208 V Models and Power Options**

Rated Input Voltage			NEMA 1 MATRIX Bypass Drive (With EMC filter)	Soft Start Bypass	3-Contactor Bypass	Drive Input Service Switch	Output Reactor	EMC Filter
			<b>Z1D1</b> 00000	W	В	G	K	N *2
	24.2	7.5	D024PN		Available	Available	Available	Included
	30.8	10	D030PN					
	46.2	15	D046PN					
	59.4	20	D059PN					
208 V	74.8	25	D074PN	Available				
3-Phase	88	30	D088PN	Available				
	114	40	D114PN					
	143	50	D143PN					
	169	60	D169PN					
	211	75	D211PN					

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

### **480 V Models and Power Options**

		Nominal HP*1	NEMA 1 MATRIX	Legend:	A = Available	N/A = Not available or not applicable		
Rated Input Voltage	Rated Output Current (Amps)		Bypass Drive	EMC Filter	Drive Input Service Switch	3-Contactor Bypass	Output Reactor	Soft Start Bypass
			<b>Z1D1</b>	N *2	G	В	K	W
	11	7.5	B011PN					
	14	10	B014PN		A			
	21	15	B021PN					
	27	20	B027PN					
	34	25	B034PN					
	40	30	B040PN					
	52	40	B052PN					
	65	50	B065PN					
480 V 3-Phase	77	60	B077PN	Included		Α	Α	Α
5 1 Hd55	96	75	B096PN		N/A			
	124	100	B124PN		N/A			
	156	125	B156PN		N/A			
	180	150	B180PN		N/A			
	240	200	B240PN		N/A			
	302	250	B302PN		N/A			
	361	300	B361PN		N/A			
	414	350	B414PN		N/A			

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

<sup>\*2.</sup> An EMC filter is included, and is internal to the MATRIX drive.

<sup>\*2.</sup> An EMC filter is included, and is internal to the MATRIX drive.

# Z1000U MATRIX Bypass Drive NEMA Type 1 (Z1D1)

### **Dimensions and Data (Z1D1)**

Batad Immut Matrix Bypas		Rated			Submittal Documents	Enclosed, NEMA 1 Bypass Data			
Rated Input Voltage	Base Ño.	Output Current	Nominal HP*1	Bypass Box No.	(Outline Drawing) (Schematic)	Overall Dimensions (in)			Mainlet (IIa)
1595	Z1D1 🗆 🗆 🗆	(Amps)				Н	W	D	Weight (lb)
	D024	24.2	7.5	W1	DD.Z1U.1.W1.01 DS.Z1D1.01	48	22	18	230
	D030	30.8	10		DD.Z1U.1.W2.01		22	18	325
	D046	46.2	15	W2		60			340
	D059	59.4	20	VVZ	DS.Z1D1.01	00	22	10	350
208 V 3-Phase	D074	74.8	25						350
3-Filase	D088	88	30	W3	DD.Z1U.1.W3.01	60	30	20	465
	D114	114	40	VVS	DS.Z1D1.01	60	30	20	475
	D143	143	50						825
	D169	169	60	F1	DD.Z1U.1.F1.01 DS.Z1D1.01	86	41	18	825
	D211	211	75		50.2151.01				1050
	B011	11	7.5		DD.Z1U.1.W1.01 DS.Z1D1.01	48	22	18	220
	B014	14	10	W1					230
	B021	21	15						230
	B027	27	20		DD.Z1U.1.W2.01	60	22	18	300
	B034	34	25						300
	B040	40	30	W2					315
	B052	52	40	VV2	DS.Z1D1.01				350
	B065	65	50						360
480 V 3-Phase	B077	77	60						375
0111400	B096	96	75	W3	DD.Z1U.1.W3.01 DS.Z1D1.01	60	30	20	475
	B124	124	100	vvs					490
	B156	156	125			86	41	32	850
	B180	180	150	F1	DD.Z1U.1.F1.01 DS.Z1D1.01				900
	B240	240	200		00.2101.01				1100
	B302	302	250		DD.Z1U.1.F2.01 DS.Z1D1.01	86	70	31	1600
	B361	361	300	F2					1750
	B414	414	350						1800

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors.

## Z1000U MATRIX Bypass Drive Type 12 (Z1D2)

### Specifications: 480 V Type 12 (Z1D2)



The Z1000U MATRIX Bypass combines excellent harmonic mitigation, input power factor control, and energy saving capabilities in a design specifically suited for use in HVAC building automation applications that require reliable motor control.

The bypass package provides a Z1000U MATRIX drive in a UL Type 12 enclosure with input circuit breaker, and 2-contactor style bypass to allow motor operation from the drive or across the line. The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications.

The Z1000U features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy. Popular building automation communication protocols BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings:
  - 480 V, 7.5 to 150 HP
- V/f Control, Open Loop Vector Control for PM
- · Overload capacity: 120% for 60 seconds
- · 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- · Stationary motor auto-tuning
- 150% starting torque capability, available from 3 to 60 Hz
- Remote speed reference (speed command)
  signal:
  - 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms)
  - 4 to 20 mA/0 to 20 mAdc (250 Ohms)

#### **Bypass Features**

- Output and bypass contactors
- · Lockable main input circuit breaker
- Thermal motor overload relay, class 20
- 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback and two adjustable wait time functions
- Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes.

#### **Design Features**

- NEC rated input / output amps
- Standard LCD Multi-lingual keypad, Full-text, Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls

- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- · Differential PID feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- · Input and output terminal status indication
- Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at fullspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status
- Adjustable carrier frequency, 4 kHz to 10 kHz
- · Programmable security code
- 8 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- · Energy Savings Monitor
- Eco-Mode to achieve near across-the-line THD and quietest operation

- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto
- Emergency override can be used as "smoke
- Fan failure detection and selectable drive
- Built-in EMC Filter
- Built-in input fuses
- Input circuit breaker (100 kAIC)
- Energy Savings Low Power Loss Design
- Compact Package
- Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS
- Optimal Speed Command Search

#### **Service Conditions**

- Input voltage: 480 Vac. -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Ambient service temperature: Type 12 (IP55): -10 °C to 40 °C (14 °F to 104 °F)
- Maximum ambient storage temperature: -20 to 60 °C (-4 to 140 °F)
- Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating

#### Standards

• UL 508A (Industrial Control Panels)


- Drive Service Switch
- Custom Nameplate
- Speed Pot (door mounted)
- 200 VA Control Power Transformer
- LonWorks Interface
- EtherNet/IP

## Z1000U MATRIX Bypass Drive Type 12 (Z1D2)

### **Model Number Configuration (Z1D2)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



### **Options (Z1D2)**

### **Enclosure Options**

Type 12

(2) The drive and configured options are provided in a UL Type 12 enclosure, large enough to accommodate any or all of the configured package options.

### **Power Options**

**Drive Service** (G) Switch

Drive service switch that removes power from the drive.

### **Control Options**

**Custom Nameplates** (W) Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.

EtherNet/IP SI-EN3

EtherNet/IP, option (D), requires the addition of an optional board. (D)

LonWorks SI-W3

(L) LonWorks, option (L), requires the addition of an optional board.

Speed pot (Z) Door mounted.

200 VA Transformer

(K) 200 VA Control Power Transformer (for customer use).

(CPT)

### Model and Power Option Selection (Z1D2)

### **480 V Models and Power Options**

		Nominal HP <sup>*1</sup>	Type 12 MATRIX Bypass	Legend: A = Available N/A = Not available or not applicable		
Rated Input Voltage	Rated Output Current (Amps)		Drive (With EMC filter) *2	EMC Filter	Drive Input Service Switch	
			Z1D200000	N*2	G	
	11	7.5	B011PN		A	
	14	10	B014PN		A	
	21	15	B021PN		A	
	27	20	B027PN		A	
	34	25	B034PN		А	
	40	30	B040PN		A	
480 V 3-Phase	52	40	B052PN	Included	A	
o i ridoo	65	50	B065PN		А	
	77	60	B077PN		A	
	96	75	B096PN		N/A	
	124	100	B124PN		N/A	
	156	125	B156PN		N/A	
	180	150	B180PN		N/A	

Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

An EMC filter is included, and is internal to the MATRIX drive.

# Z1000U MATRIX Bypass Drive Type 12 (Z1D2)

### **Dimensions and Data (Z1D2)**

	Matrix Bypass	Rated	Nominal HP *1	Bypass Box No.	Submittal Documents (Outline Drawing) (Schematic)	Enclosed, Type 12 Bypass Data			
Voltage Bas	Base No.	Output Current				Overall Dimensions (in)			Weight (lb)
	Z1D2□□□□	(Amps)				Н	W	D	vveignt (ib)
	B011	11	7.5						217
	B014	14	10	W1	DD.Z1U.2.W1.01	40.0	23.3	19.1	218
	B021	21	15	VVI	DS.Z1D2.01	40.2			218
	B027	27	20						220
	B034	34	25	W2	DD.Z1U.2.W2.01 DS.Z1D2.01	47.0	27.3	21.6	279
	B040	40	30						308
480 V 3-Phase	B052	52	40						312
<b>0</b> 1 11400	B065	65	50						326
	B077	77	60						327
	B096	96	75	14/2	DD.Z1U.2.W3.01 DS.Z1D2.01	56.2	33.3	27.0	497
	B124	124	100	W3					501
	B156	156	125	F1	DD.Z1U.2.F1.01 DS.Z1D2.01	84.0	37.9	26.9	923
	B180	180	150						938

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors.

## Z1000U MATRIX Bypass Drive NEMA Type 3R (Z1D3)

### Specifications: 208 and 480 V NEMA Type 3R (Z1D3)



The Z1000U MATRIX Bypass combines excellent harmonic mitigation, input power factor control, and energy saving capabilities in a design specifically suited for use in HVAC building automation applications that require reliable motor control.

The bypass package provides a Z1000U MATRIX drive in a NEMA 3R (UL Type 3R) enclosure with input circuit breaker, and 2-contactor style bypass to allow motor operation from the drive or across the line. The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications.

The Z1000U features HVAC application-specific software macros, a Hand-Off-Auto LCD keypad, and a real time clock for system accuracy. Popular building automation communication protocols BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings:
   208 V, 7.5 to 75 HP
   480 V, 7.5 to 350 HP
- V/f Control, Open Loop Vector Control for PM
- Overload capacity: 120% for 60 seconds
- 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- · Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- Stationary motor auto-tuning
- 150% starting torque capability, available from 3 to 60 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms)
  - 4 to 20 mA/0 to 20 mAdc (250 Ohms)

#### **Bypass Features**

- · Output and bypass contactors
- Lockable main input circuit breaker
- · Thermal motor overload relay, class 20
- 115 Vac control transformer, fused
- Drive H/O/A keypad used for bypass control
- Damper control circuit with end of travel feedback and two adjustable wait time functions
- · Selectable energy savings mode
- No load detection (loss of load) fully monitored in drive and bypass modes.

#### **Design Features**

- NEC rated input / output amps
- Standard LCD Multi-lingual keypad, Full-text, Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls

- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- · Differential PID feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy
- Feedback signal inverse and square root capability
- · Input and output terminal status indication
- · Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at fullspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- · Serial communication status
- Adjustable carrier frequency, 4 kHz to 10 kHz
- Programmable security code
- 8 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- · Energy Savings Monitor
- Eco-Mode to achieve near across-the-line THD and quietest operation

- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
  - "Bumpless" transfer between Hand and Auto
- Emergency override can be used as "smoke
- Fan failure detection and selectable drive
- · Built-in EMC Filter
- Built-in input fuses
- Input circuit breaker (100 kAIC)
- Energy Savings Low Power Loss Design
- · Compact Package
- · Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS
- Optimal Speed Command Search

#### **Service Conditions**

- Input voltage: 208 Vac. 480 Vac. -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Ambient service temperature: NEMA 3R: -10 °C to 40 °C (14 °F to 104 °F)
- Maximum ambient storage temperature: -20 to 60 °C (-4 to 140 °F)
- Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet)

#### Standards


UL 508A (Industrial Control Panels)

- 3-Contactor Bypass
- Drive Service Switch
- 5% Output Reactor
- Soft-start Bypass
- Custom Nameplate
- Speed Pot (door mounted)200 VA Control Power Transformer
- LonWorks Interface
- EtherNet/IP
- Keypad Viewing Window
- Surge Suppressor
- Space Heater

## Z1000U MATRIX Bypass Drive NEMA Type 3R (Z1D3)

### **Model Number Configuration (Z1D3)**

- Step 1. Complete the Base Number for the voltage and current rating.
- **Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.
- **Step 3.** Find the list price for the Base Number selected from the following pages. Add the list price of each selected option to this base price.



<sup>\*</sup> An EMC filter is internal to the Z1000U drive.

### Options (Z1D3)

### **Enclosure Options**

NEMA 3R

(3) The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.

## **Power Options**

Drive Input Circuit	(B, G)		r a 3-contactor bypass that removes power from the drive, select option (B). ive service switch that removes power from the drive, select option (G).						
Output Reactor	(K)	is a	No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long lead-lengths or noise reduction).						
Soft Start Bypass	(W) *1	mo rec by me No syr - z - z	ovides a solid-state adjustable soft starter for use when switching to bypass ode. Option (W) provides a solid-state soft-starter with adjustable ramp to duce mechanical system stress typically associated with across-the-line pass motor starts. Select option (W) if the application cannot tolerate the echanical load stress caused by across-the-line bypass motor starts.  Ite *1: The following Z1D1 models have a short circuit withstand rating of 65 kA RMS mmetrical when option W is specified:  Z1D3B011 to Z1D3B156  Z1D3D024 to Z1D3D143  her Z1D1 models have a short circuit withstand rating of 100 kA RMS symmetrical when tion W is specified.						
Surge Suppressor	(7)	thr	This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.						
Space Heater	(3)	Th	is option helps reduce condensation.						
<b>Control Options</b>									
Custom Nameplates		(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.						
EtherNet/IP SI-EN3		(D)	EtherNet/IP, option (D), requires the addition of an optional board.						
LonWorks SI-W3		(L)	LonWorks, option (L), requires the addition of an optional board.						
Speed pot		(Z)	Door mounted.						
200 VA Transformer	r	(K)	200 VA Control Power Transformer (for customer use).						

## Z1000U MATRIX Bypass Drive NEMA Type 3R (Z1D3)

Keypad Viewing Window (M) The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.

#### **Options (Field Install Only)**

Freestanding Leg Kit NEMA 3R	UUX001158	12 in. Leg Kit: This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.
	UUX001159	<b>30 in. Leg Kit:</b> This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.

### **Model and Power Option Selection (Z1D3)**

### **208 V Models and Power Options**

			NEMA 3R		Legend: A =	Available	N/A = Not av	ailable or no	t applicable	
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP*1	MATRIX Bypass Drive (With EMC filter)*2	EMC Filter	Drive Input Service Switch	3-Contactor Bypass	Output Reactor	Soft Start Bypass	Surge Suppressor	Space Heater
			Z1D3	N *2	G	В	K	W	7	3
	24.2	7.5	D024PN							
	30.8	10	D030PN		A	A	A	A	A	A
	46.2	15	D046PN							
	59.4	20	D059PN							
208 V	74.8	25	D074PN	Included						
3-Phase	88	30	D088PN	included	N/A		A	A	A	А
	114	40	D114PN	N/A N/A	N/A					
	143	50	D143PN		N/A	1				
	169	60	D169PN		N/A					
	211	75	D211PN		N/A					

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

#### **480 V Models and Power Options**

			NEMA 3R		Legend: A =	Available	N/A = Not av	ailable or no	t applicable	
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP*1	MATRIX Bypass Drive (With EMC filter)*2	EMC Filter	Drive Input Service Switch	3-Contactor Bypass	Output Reactor	Soft Start Bypass	Surge Suppressor	Space Heater
			Z1D3	N *2	G	В	K	W	7	3
	11	7.5	B011PN							
	14	10	B014PN							
	21	15	B021PN							
	27	20	B027PN							
	34	25	B034PN		Α					
	40	30	B040PN							
	52	40	B052PN							
	65	50	B065PN							
480 V 3-Phase	77	60	B077PN	Included		Α	Α	Α	Α	Α
0 1 11000	96	75	B096PN		N/A					
	124	100	B124PN		N/A					
	156	125	B156PN		N/A					
	180	150	B180PN		N/A					
	240	200	B240PN		N/A					
	302	250	B302PN		N/A					
	361	300	B361PN		N/A					
	414	350	B414PN		N/A					

<sup>1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

<sup>\*2.</sup> Includes an internal EMC filter.

<sup>\*2.</sup> Includes an internal EMC filter.

## Z1000U MATRIX Bypass Drive NEMA Type 3R (Z1D3)

### **Dimensions and Data (Z1D3)**

Refer to the product page on the Yaskawa website for dimension, weight, and schematic diagram data depending on drive model and installed options.

Use document PD.Z1000.01 for 208 V models

Use document PD.Z1000.02 for 480 V models

## Z1000U MATRIX Configured Drive NEMA Type 1 (Z1E1)

#### Specifications: 208 and 480 V NEMA Type 1 (Z1E1)



The Z1000U Configured variable-speed MATRIX drive combines excellent harmonic mitigation, input power factor control, and energy saving capabilities in a design allowing flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000U MATRIX drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input disconnect switch and space for several power options inside a NEMA 1 (UL Type 1) enclosure.

The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications.

Popular building automation communication protocols BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2 and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings:
   208 V, 7.5 to 75 HP
   480 V, 7.5 to 350 HP
- V/f Control, Open Loop Vector Control for PM
- · Overload capacity: 120% for 60 seconds
- 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- · Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- Up/down floating point control capability
- Stationary motor auto-tuning

#### **Design Features**

- NEC rated input / output amps
- Standard LCD Multi-lingual keypad, Full-text, Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- · Differential PID feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy

- Feedback signal inverse and square root capability
- Input and output terminal status indication
- · Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at fullspeed
- · "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- 150% starting torque capability, available from 3 Hz
- Remote speed reference (speed command) signal:
- 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms)
- 4 to 20 mA/0 to 20 mAdc (250 Ohms)
- Adjustable carrier frequency, from 4 kHz to 10 kHz
- Programmable security code
- 8 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- · Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- · 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- Energy Savings Monitor
- Eco-Mode to achieve near across-the-line THD and quietest operation
- Flash upgradeable firmware
- Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function

- Fan failure detection and selectable drive action
- · Built-in EMC Filter
- · Built-in input fuses
- Input disconnect switch
- Energy Savings Low Power Loss Design
- Compact Package
- Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- · Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS (with optional circuit breaker)
- Optimal Speed Command Search

#### **Service Conditions**

- Input voltage: 208 Vac, 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Maximum ambient service temperature NEMA 1: -10 to 40 °C (14 to 104 °F)
- Maximum ambient storage temperature: -20 to 60 °C (-4 to 140 °F)
- Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating
- Service factor: 1.0

#### Standards

• UL 508A (Industrial Control Panels)

#### Options


- 5% Output Reactor
- Lockable input Circuit Breaker (100 kAIC)
- Custom Nameplate
- Speed Pot (door mounted)
- 200 VA Control Power Transformer
- LonWorks Interface
- EtherNet/IP

## Z1000U MATRIX Configured Drive NEMA Type 1 (Z1E1)

### **Model Number Configuration (Z1E1)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



#### Options (Z1E1)

#### **Power Options**

Output Reactor (K) No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long lead-lengths or noise reduction).

Circuit Breaker 100 kAIC (M) Lockable input Circuit Breaker (100 kAIC panel rating).

## **Control Options**

Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.
EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Speed pot	(Z)	Door mounted.
200 VA Transformer (CPT)	(K)	200 VA Control Power Transformer (for customer use).

## Z1000U MATRIX Configured Drive NEMA Type 1 (Z1E1)

### **Model and Power Option Selection (Z1E1)**

### **208 V Models and Power Options**

Rated Input Voltage	Rated Output Current (Amps)	Nominal HP*1	NEMA 1 Configured Matrix (With EMC filter)	EMC Filter	Circuit Breaker (100 kAIC)	Output Reactor
			Z1E100000	N *2	М	K
	24.2	7.5	D024PN			
	30.8	10	D030PN			
	46.2	15	D046PN			
	59.4	20	D059PN			
208 V	74.8	25	D074PN	Induded	Available	Available
3-Phase	88	30	D088PN	Included	Available	Available
	114	40	D114PN			
	143	50	D143PN			
	169	60	D169PN			
	211	75	D211PN			

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

#### **480 V Models and Power Options**

Rated Input Voltage	Rated Output Current (Amps)	Nominal HP *1	NEMA 1 Configured Matrix (With EMC filter)	EMC Filter	Circuit Breaker (100 kAIC)	Output Reactor
			Z1E1000000	N*2	М	K
	11	7.5	B011PN			
	14	10	B014PN			
	21	15	B021PN			
	27	20	B027PN			
	34	25	B034PN			
	40	30	B040PN			
	52	40	B052PN			
	65	50	B065PN			
480 V 3-Phase	77	60	B077PN	Included	Available	Available
0 1 11000	96	75	B096PN			
	124	100	B124PN			
	156	125	B156PN			
	180	150	B180PN			
	240	200	B240PN			
	302	250	B302PN			
	361	300	B361PN			
	414	350	B414PN			

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

<sup>\*2.</sup> An EMC filter is included, and is internal to the MATRIX drive.

<sup>\*2.</sup> An EMC filter is included, and is internal to the MATRIX drive.

## **Dimensions and Data (Z1E1)**

Detect law 1	Matrix Configured	Rated		D	Submittal Documents	Enclosed, NEMA 1 Configured Data			
Rated Input Voltage	Base No.	Output Current	Nominal HP*1	Bypass Box No.	(Outline Drawing)	Overall Dimension		ions (in)	Weight (lb)
	Z1E1□□□□	(Amps)			(Schematic)	Н	W	D	weight (ib)
	D024	24.2	7.5	W1	DD.Z1U.1.W1.01 DS.Z1E1.01	48	22	18	210
	D030	30.8	10						300
	D046	46.2	15	W2	DD.Z1U.1.W2.01	60	22	18	305
	D059	59.4	20	VVZ	DS.Z1E1.01	60	22	10	315
208 V 3-Phase	D074	74.8	25						315
J-Filase	D088	88	30	W3	DD.Z1U.1.W3.01	60	30	20	420
	D114	114	40	VV3	DS.Z1E1.01	00	30	20	430
	D143	143	50		55 744 4 54 64		41	32	745
	D169	169	60	F1	DD.Z1U.1.F1.01 DS.Z1E1.01	86			745
	D211	211	75						945
	B011	11	7.5		DD.Z1U.1.W1.01 DS.Z1E1.01	48	22	18	200
	B014	14	10	W1					210
	B021	21	15						210
	B027	27	20			60	22	18	270
	B034	34	25						270
	B040	40	30	W2	DD.Z1U.1.W2.01				285
	B052	52	40	VVZ	DS.Z1E1.01	00		10	315
400.14	B065	65	50						325
480 V 3-Phase	B077	77	60						340
	B096	96	75	W3	DD.Z1U.1.W3.01	60	30	20	425
	B124	124	100	****	DS.Z1E1.01	00		20	440
	B156	156	125	F1	DD 7411.4 E4.04				765
	B180	180	150		DD.Z1U.1.F1.01 DS.Z1E1.01	86	41	32	810
	B240	240	200						990
	B302	302	250		DD 74114 F0 04		70	31	1440
	B361	361	300	F2	DD.Z1U.1.F2.01 DS.Z1E1.01	86			1575
	B414	414	350		50.2121.01				1620

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors.

## Z1000U MATRIX Configured Drive Type 12 (Z1E2)

#### Specifications: 480 V Type 12 (Z1E2)



The Z1000U Configured variable-speed MATRIX drive combines excellent harmonic mitigation, input power factor control, and energy saving capabilities in a design allowing flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000U MATRIX drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input disconnect switch and space for several power options inside a UL Type 12 enclosure.

The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications.

Popular building automation communication protocols BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately

#### **Performance Features**

- VT Ratings:
  - 480 V, 7.5 to 150 HP
- · V/f Control, Open Loop Vector Control for PM
- · Overload capacity: 120% for 60 seconds
- 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- Adjustable accel/decel: 0.1 to 6000 seconds
- · Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- · Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- · Up/down floating point control capability
- · Stationary motor auto-tuning

#### **Design Features**

- NEC rated input / output amps
- Standard LCD Multi-lingual keypad, Full-text, Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- · Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- · Differential PID feedback feature
- Sleep function in both closed loop and open loop control
- Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy

- Feedback signal inverse and square root capability
- Input and output terminal status indication
- · Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at fullspeed
- "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- 150% starting torque capability, available from 3 Hz
- Remote speed reference (speed command) signal:
- 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms)
- 4 to 20 mA/0 to 20 mAdc (250 Ohms)
- Adjustable carrier frequency, from 4 kHz to 10 kHz
- · Programmable security code
- 8 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- · Serial communication status
- · No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- Energy Savings Monitor
- Eco-Mode to achieve near across-the-line THD and quietest operation
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function

- Fan failure detection and selectable drive action
- Built-in EMC Filter
- · Built-in input fuses
- · Input disconnect switch
- Energy Savings Low Power Loss Design
- Compact Package
- Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- · Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- · Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS (with optional circuit breaker)
- · Optimal Speed Command Search

#### Service Conditions

- Input voltage: 480 Vac, -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Maximum ambient service temperature UL Type 12 (IP55): -10 to 40 °C (14 to 104 °F)
- Maximum ambient storage temperature: -20 to 60 °C (-4 to 140 °F)
- · Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet); higher by derating
- Service factor: 1.0

#### Standards

• UL 508A (Industrial Control Panels)


#### Options

- Lockable input Circuit Breaker (100 kAIC)
- Custom Nameplate
- Speed Pot (door mounted)
- 200 VA Control Power Transformer
- LonWorks Interface
- EtherNet/IP

### **Model Number Configuration (Z1E2)**

Step 1. Complete the Base Number for the voltage and current rating.

**Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.



<sup>\*</sup> An EMC filter is internal to the Z1000U drive.

#### **Options (Z1E2)**

#### **Power Options**

Circuit Breaker 100 kAIC

(M) Lockable input Circuit Breaker (100 kAIC panel rating).

## Z1000U MATRIX Configured Drive Type 12 (Z1E2)

### **Control Options**

Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.
EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Speed pot	(Z)	Door mounted.
200 VA Transformer (CPT)	(K)	200 VA Control Power Transformer (for customer use).

## **Model and Power Option Selection (Z1E2)**

### **480 V Models and Power Options**

			Type 12 Configured	Legend: A = Available N/A = Not availab or not applicable		
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP*1	Matrix (With EMC filter)*2	Circuit Breaker (100 kAIC)	EMC Filter	
			Z1E200000	N *2	М	
	11	7.5	B011PN			
	14	10	B014PN			
	21	15	B021PN			
	27	20	B027PN			
	34	25	B034PN			
	40	30	B040PN			
480 V 3-Phase	52	40	B052PN	Included	A	
o i nasc	65	50	B065PN			
	77	60	B077PN			
	96	75	B096PN			
	124	100	B124PN			
	156	125	B156PN			
	180	150	B180PN			

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

<sup>\*2.</sup> An EMC filter is included, and is internal to the MATRIX drive.

## Z1000U MATRIX Configured Drive Type 12 (Z1E2)

### **Dimensions and Data (Z1E2)**

	Matrix Configured	Rated			Submittal Documents	Enclos	ed, Type	12 Confi	gured Data
Rated Input Voltage	Base No.	Output Current	Nominal HP*1	Bypass Box No.	ypass Box (Outline Drawing)		Overall Dimensions (in)		
ronago	Z1E2□□□□	(Amps)			(Schematic)	Н	W	D	Weight (lb)
	B011	11	7.5						214
	B014	14	10	W1	DD.Z1U.2.W1.01 DS.Z1E2.01	40.2	23.3	19.1	214
	B021	21	15	VVI		40.2	23.3	19.1	215
	B027	27	20						215
	B034	34	25		DD.Z1U.2.W2.01 DS.Z1E2.01		27.3		269
	B040	40	30						296
480 V 3-Phase	B052	52	40	W2		47.0		21.6	300
0 1 11000	B065	65	50		20.2.220.				308
	B077	77	60						311
	B096	96	75	14/2	DD.Z1U.2.W3.01	56.2	22.2	27.0	481
	B124	124	100	W3	DS.Z1E2.01	30.2	33.3		485
	B156	156	125	F1	DD.Z1U.2.F1.01	84.0	37.9	26.9	888
	B180	180	150	FI	DS.Z1E2.01	84.0	37.9	20.9	897

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors.

## Z1000U MATRIX Configured Drive NEMA Type 3R (Z1E3)

#### Specifications: 208 and 480 V NEMA Type 3R (Z1E3)



The Z1000U Configured variable-speed MATRIX drive combines excellent harmonic mitigation, input power factor control, and energy saving capabilities in a design allowing flexibility when providing the features and options commonly specified by facility designers.

The configured package provides a Z1000U MATRIX drive containing HVAC application-specific software macros, a real time clock, and Hand-Off-Auto LCD keypad with an input disconnect switch and space for several power options inside a NEMA 3R (UL Type 3R) enclosure.

The Z1000U HVAC MATRIX drive incorporates MATRIX technology to directly convert input AC voltage to output AC voltage. The Z1000U HVAC MATRIX drive offers real choices and benefits for green HVAC applications.

Popular building automation communication protocols BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus are embedded in the drive. Interface cards for LonWorks and EtherNet/IP communications are offered separately.

#### **Performance Features**

- VT Ratings:
   208 V, 7.5 to 75 HP
   480 V, 7.5 to 350 HP
- · V/f Control, Open Loop Vector Control for PM
- Overload capacity: 120% for 60 seconds
- 0-400 Hz Output Frequency
- DC Injection braking: at start or stop, adjustable, current limited (anti-windmilling)
- · Adjustable accel/decel: 0.1 to 6000 seconds
- · Controlled speed range: 40:1
- Critical frequency rejection capability: 3 selectable, adjustable bands
- Torque limiting: 0 to 300%
- Power loss ride through: 2 seconds
- Auto restart after power loss or resettable fault, selectable, programmable
- Up/down floating point control capability
- Stationary motor auto-tuning

#### **Design Features**

- NEC rated input / output amps
- Standard LCD Multi-lingual keypad, Full-text, Hand-Off-Auto with Copy (Read/Write) Function
- Built-In real time clock for time and date stamping events along with timer functions for starting, stopping and speed changes without the need for external controls
- Volt meter, ammeter, kilowatt meter elapsed run time meter and heat sink temperature monitoring functions
- Two internal (PID) Controls
- Drive internal PID closed loop control with selectable engineering units
- Independent PID control for use with external device
- · Differential PID feedback feature
- Sleep function in both closed loop and open loop control
- · Feedback signal low pass filter
- Feedback signal loss detection and selectable response strategy

- Feedback signal inverse and square root capability
- · Input and output terminal status indication
- · Diagnostic fault indication
- VFD efficiency: 96% at half-speed; 98% at fullspeed
- · "S-curve" soft start / soft stop capability
- Serial communication loss detection and selectable response strategy
- 150% starting torque capability, available from 3 Hz
- Remote speed reference (speed command) signal:
  - 0 to 10 Vdc/-10 to 10 Vdc (20 K Ohms)
  - 4 to 20 mA/0 to 20 mAdc (250 Ohms)
- Adjustable carrier frequency, from 4 kHz to 10 kHz
- Programmable security code
- 8 programmable multi-function input terminals (24 Vdc) providing 60+ programmable features, including:
  - Customer Safeties
  - BAS / Damper Interlock
  - Emergency Override
  - Preset Speed
  - PI control enable / disable
- 2x Form A and 1x Form C programmable multifunction output relays (Rated 1 amp @ 250 Vac & 30 Vdc), providing 50+ functions, including:
  - Damper control
  - Hand/Auto Status
  - Contactor Control for External Bypass
  - Overtorque/undertorque detection
- · Serial communication status
- No load detection (broken belt alert)
- One fixed "Fault" form C output relay (Rated 1 amp @ 250 Vac & 30 Vdc)
- · 6 preset speeds
- Built-in BACnet (BTL certified), Siemens APOGEE FLN, Johnson Controls Metasys N2, and MEMOBUS/Modbus communication
- · Energy Savings Monitor
- Eco-Mode to achieve near across-the-line THD and quietest operation
- Flash upgradeable firmware
- · Customizable monitor display
- Heat sink over temperature speed foldback feature
- "Bumpless" transfer between Hand and Auto modes
- Emergency override can be used as "smoke purge" function

- Fan failure detection and selectable drive action
- · Built-in EMC Filter
- · Built-in input fuses
- Input disconnect switch
- Energy Savings Low Power Loss Design
- Compact Package
- Unity Power Factor Control
- IEEE-519 Compliant (<5% TDD) Harmonic Characteristics
- · Low Harmonics over Wide Speed Range
- DriveWizard® HVAC Software
- Removable Terminal Block with Memory
- High Reliability with an MTBF of 28 Years
- Short Circuit Withstand Rating: 100K RMS (with optional circuit breaker)
- Optimal Speed Command Search

#### **Service Conditions**

- Input voltage: 208 Vac. 480 Vac. -15/+10%
- Input frequency: 50/60 Hz ±3% (Frequency fluctuation rate: 1 Hz/100 ms or less)
- Maximum ambient service temperature NEMA 3R: -10 to 40 °C (14 to 104 °F)
- Maximum ambient storage temperature: -20 to 60 °C (-4 to 140 °F)
- · Humidity: 0% to 95%, non-condensing
- Altitude: to 1000 meters (3300 feet)
- Service factor: 1.0

#### Standards

• UL 508A (Industrial Control Panels)


#### Options

- 5% Output Reactor
- Lockable input Circuit Breaker (100 kAIC)
- · Custom Nameplate
- Speed Pot (door mounted)
- 200 VA Control Power Transformer
- · LonWorks Interface
- EtherNet/IP
- Keypad Viewing Window
- Surge Suppressor
- Space Heater

## Z1000U MATRIX Configured Drive NEMA Type 3R (Z1E3)

### **Model Number Configuration (Z1E3)**

- Step 1. Complete the Base Number for the voltage and current rating.
- **Step 2.** Add the Option Code letter for each required option. If an option is not wanted, no character is inserted in that position.
- **Step 3.** Find the list price for the Base Number selected from the following pages. Add the list price of each selected option to this base price.



<sup>\*</sup> An EMC filter is internal to the Z1000U drive.

### Options (Z1E3)

#### **Enclosure Options**

NEMA 3R

(3) The drive and configured options are provided in a NEMA Type 3R ventilated enclosure, large enough to accommodate any or all of the Configured package options.

#### **Power Options**

Output Reactor

(K) No form of output impedance is normally required. A 5% load reactor, option (K), is available if additional output impedance is desired (usually for long lead-lengths or noise reduction).

Circuit Breaker 100 kAIC

(M) Lockable input Circuit Breaker (100 kAIC panel rating).

Surge Suppressor	(7)	This option provides a degree of protection from transient surges coming through the power line cables. Lightning strikes are the most common source of surges.
Space Heater	(3)	This option helps reduce condensation.
Control Options		
Custom Nameplates	(W)	Custom engraved nameplates with white lettering on black lamicoid are available with option (W), for special tagging purposes (Example: "AHU #1"). Note that this option requires the text to be specified by the customer.
EtherNet/IP SI-EN3	(D)	EtherNet/IP, option (D), requires the addition of an optional board.
LonWorks SI-W3	(L)	LonWorks, option (L), requires the addition of an optional board.
Speed pot	(Z)	Door mounted.
200 VA Transformer (CPT)	(K)	200 VA Control Power Transformer (for customer use).
Keypad Viewing Window	(M)	The digital drive keypad is mounted on the outside of the NEMA 3R enclosure door. This option provides a viewing window that is hinged and lockable.

### **Options (Field Install Only)**

Kit NEMA 3R		mounted on legs so that the control can be freestanding and off the ground.  Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.				
	UUX001159	<b>30 in. Leg Kit:</b> This option allows the NEMA 3R wall-mount enclosures to be mounted on legs so that the control can be freestanding and off the ground. Either kit can be used on any of the wall-mount enclosures. Floor-mount enclosures come standard with freestanding legs.				

Freestanding Leg UUX001158 12 in. Leg Kit: This option allows the NEMA 3R wall-mount enclosures to be

## Z1000U MATRIX Configured Drive NEMA Type 3R (Z1E3)

### **Model and Power Option Selection (Z1E3)**

#### **208 V Models and Power Options**

			NEMA 3R	Legend: A = Available		N/A = Not available or not applicable		
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP <sup>*1</sup>	Configured Matrix (With EMC filter)	EMC Filter	Circuit Breaker (100 kAIC)	Output Reactor	Surge Suppressor	Space Heater
			Z1E3	N *2	М	K	7	3
	24.2	7.5	D024PN	Included	А	А	Α	A
208 V 3-Phase	30.8	10	D030PN					
	46.2	15	D046PN					
	59.4	20	D059PN					
	74.8	25	D074PN					
	88	30	D088PN					
	114	40	D114PN					
	143	50	D143PN					
	169	60	D169PN					
	211	75	D211PN					

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 208 volts.

#### **480 V Models and Power Options**

			NEMA 3R	Legend: A = Available N/A = Not available or not applicable					
Rated Input Voltage	Rated Output Current (Amps)	Nominal HP*1	Configured Matrix (With EMC filter)	EMC Filter	Circuit Breaker (100 kAIC)	Output Reactor	Surge Suppressor	Space Heater	
			Z1E3	N *2	M	K	7	3	
	11	7.5	B011PN	Included	A	A	A	A	
	14	10	B014PN						
	21	15	B021PN						
	27	20	B027PN						
	34	25	B034PN						
	40	30	B040PN						
	52	40	B052PN						
	65	50	B065PN						
480 V 3-Phase	77	60	B077PN						
o i nacc	96	75	B096PN						
	124	100	B124PN						
	156	125	B156PN						
	180	150	B180PN						
	240	200	B240PN						
	302	250	B302PN						
	361	300	B361PN						
	414	350	B414PN						

<sup>\*1.</sup> Horsepower rating is based on standard NEMA B, 4-pole motor design as represented in NEC table 430.150 Full-Load Current, Three-Phase Alternating Current Motors at 480 volts.

<sup>\*2.</sup> Includes an internal EMC filter.

<sup>\*2.</sup> Includes an internal EMC filter.

### **Dimensions and Data (Z1E3)**

Refer to the product page on the Yaskawa website for dimension, weight, and schematic diagram data depending on drive model and installed options.

Use document PD.Z1000.05 for 208 V models

Use document PD.Z1000.06 for 480 V models

## **Technical Training**

In today's world of global competition, it is impossible for a company to survive without "state-of-the-art" technically trained associates and customers. Yaskawa Technical Training Services (TTS) is comprised of engineers who are specialists in their field.

Yaskawa America has three training facilities in the United States. The primary training facility is in Yaskawa America's North American Headquarters in Waukegan, Illinois (45 miles north of Chicago, 50 miles south of Milwaukee). This facility has six training rooms; two lecture halls, two training rooms and two training labs.

Besides the possibility of attending training classes in Waukegan and Los Angeles, Yaskawa America can also bring training to the customer. On-site classes are available in two varieties. The first is to duplicate the official training classes at the customer's location. Full functioning demo units, data projector, computer and documentation can be shipped to recreate the official class on-site. The second variety is road show training. Road show training is a one-day training class that is specifically tailored to the students' needs and questions. Only basic demos are used and the topics covered in class are generated by the students in attendance.

The Yaskawa Virtual Training Room is another training option. All you need is an Internet connection and a telephone. This is a live, interactive training class, which gives you the ability to talk to the instructor as well as other students. The Internet connection allows us to show slides and demonstrate software packages. The telephone is for the audio portion of the training class. Web classes can be found on the Yaskawa formal training schedule and can also be done on-demand, per the time and preference of the customer.

To enroll, contact Technical Training Services.

Phone: 1-800-YASKAWA (1-800-927-5292), then dial 2 for "Drives" and 4 for "Training"

Phone: 1-800-YASKAWA (1-800-927-5292), then dial 2 for "Drives" and 4 for "Training"

E-mail: training@yaskawa.com

Check out the latest class schedule and cut sheets at www.yaskawa.com

# **YASKAWA**



Yaskawa America, Inc. Drives & Motion Division

2121 Norman Drive South
Waukegan, IL 60085
1-800-YASKAWA (927-5292) • Local: 847-887-7000 • Fax: 1-847-887-7310

www.yaskawa.com

